

LA-UR-12-24264

Approved for public release; distribution is unlimited.

Title: Status of Fukushima Muon Tomography Project

Author(s): Milner, Edward C.
Bacon, Jeffrey D.
Borozdin, Konstantin N.
Miyadera, Haruo
Morris, Christopher
Perry, John O.

Intended for: Meeting with TEPCO personnel at LANL



Disclaimer:

Los Alamos National Laboratory, an affirmative action/equal opportunity employer, is operated by the Los Alamos National Security, LLC for the National Nuclear Security Administration of the U.S. Department of Energy under contract DE-AC52-06NA25396. By approving this article, the publisher recognizes that the U.S. Government retains nonexclusive, royalty-free license to publish or reproduce the published form of this contribution, or to allow others to do so, for U.S. Government purposes. Los Alamos National Laboratory requests that the publisher identify this article as work performed under the auspices of the U.S. Department of Energy. Los Alamos National Laboratory strongly supports academic freedom and a researcher's right to publish; as an institution, however, the Laboratory does not endorse the viewpoint of a publication or guarantee its technical correctness.

Status of Fukushima Muon Tomography Project

LANL/TEPCO Meeting

Los Alamos, NM USA

Cas Milner

Reactor Imaging Team: Jeff Bacon, Konstantin Borozdin, Haruo Miyadera, Chris Morris, John Perry

***Los Alamos National Laboratory
P-25, Sub-Atomic Physics Group***

Outline

■ Previous developments

- Concept demonstration
- Simulation
- TEPCO-LANL Fukushima radiation measurements

■ Recent developments

- Material identification analysis
- 3-d visualization
- LANL-CC2 agreement
- Simulation

■ Future developments

- Imaging small reactor
- Site engineering and operations (“small fuku”)
- New FPGA code to purify data read-out

LANL has been working on reactor muon imaging since April, 2011.

■ **April, 2011**

- First version of reactor muon imaging proposal
- Communications with Japanese scientists and government officials

■ **August, 2011**

LANL

- Demonstration experiment shows muon tomography imaging of reactors possible
- Confirmed by simulation models

■ **February, 2012**

DOE

- Washington, DC muon imaging workshop

■ **May, 2012**

DOE

- Tsukuba, Japan muon imaging workshop
- TEPCO-LANL measurements at reactor site

■ **August, 2012**

LANL

- Los Alamos, NM, TEPCO-LANL workshop

CC2

Recent LANL work has answered critical questions.


- **Combining muon scattering and transmission analysis improves material identification**
 - Analyzing LANL data for both muon transmission and scattering shows amount and location of each kind of material: fuel, concrete, steel, water, etc.
 - Demonstration measurement completed
 - Paper submitted to physics journal.
 - Muon analysis could provide guidance for fuel extraction.
- **GEANT4 simulation shows images of melted fuel**
 - Simulations performed for fuel-condition scenarios suggested by Sugawara, *et al.*
 - Muon tomography analysis shows good detail of fuel location.

LANL demonstration apparatus approximated the Fukushima Daiichi reactor configuration.


- Shielding
 - Concrete blocks (~ 2.7 m) similar to 3-m reactor containment shielding
- Targets
 - 70-cm of Pb ($\sim 126 L_{rad}$) equivalent to ~ 2.8 -m thick reactor fuel ($\sim 124 L_{rad}$)
 - Several tons of Pb bricks in various shapes
 - Approximation to melted masses of uranium in reactor
- Detectors (5-cm-diameter aluminum drift tubes, sealed, filled with gas)
 - Placement and size approximated possible Fukushima deployment:
 - Demonstration: ~ 7 -m separation, 1.2-m x 1.2-m detector ($\sim 1.4\text{-m}^2$)
 - Fukushima: ~ 50 -m separation, 8.4-m x 8.4-m detector ($\sim 70.6\text{-m}^2$)
 - Angular acceptance: between 11° and 26° above horizon
 - Decision Sciences Corporation can manufacture complete system
 - Drift tubes (can make ~ 300 per day per shift)
 - Electronics
 - Software (data acquisition, online processing, real time reconstruction)

The experiment used previously constructed detectors.

- Two sets of trackers (MMT – Muon Mini-Tracker)
- Each tracker set has 3 x-y pairs planes, for a 6-fold tracking coincidence, in and out.
- Tracker sets moved to “mock reactor”.
- One set placed high on shielding, to track incoming muons.
- Other set placed low on the “exit” side of the shielding.



Concrete shielding thickness was similar to reactor containment shielding.



Muon
tracker
position

1.83 m


Muon
tracker
position

Target region


The demonstration apparatus approximated the cross section of a reactor.

- Concrete
- Muon mini-tracker (MMT) set
- Target region

All distances in meters (m)
Angles are in degrees, and are with respect to horizon.



The multiple scattering distribution is wider for high-Z objects;
muon scattering distribution shows material composition.




A target of 80-, 40-, and 20-cm of lead (Pb) was imaged.

- 210 hours of data




Experimental data runs ##49-55




An 80-cm-thick Pb target, with “conical void” was imaged – an attempt to approximate TMI core.

- 4.5 tons of Pb
- 500 hours data (20 days)



Experimental data for conical void



LANL continues working on critical issues.

- **Muon mini-tracker (MMT) will be used to image small reactor**
 - Collaboration with University of New Mexico (Albuquerque) Dept. of Nuclear Engineering. Will measure image of reactor structure.
 - Uranium powder core, low power
 - Radiation environment similar to Fukushima Daiichi – good test of system.
- **Proposing engineering and operations systems test at Fukushima site**
 - Determine detector shielding requirements.
 - Operate at site – electronics, data acquisition, experiment control.
 - Demonstration system operations at Fukushima site
- **Test efficiency of FPGA firmware signal coincidence**
 - New FPGA code – standard technique for high-rate experiments
 - Track coincidence to lower single-hit radiation background rate and data read-out
 - Test at LANL

Engineering tests will reduce or eliminate project risks.

■ **Muon tomography is a mature technology deployed in shipping ports**

- Robust system – operates outdoors.
- Fukushima Daiichi site is harsher – radiation and clean-up site
- Demonstrating solutions to operating in harsh conditions will lowering risk.

■ **Engineering test components and assumptions:**

- Detector system components will be purchased from vendors
- System will be assembled and tested at LANL
- TEPCO personnel will be trained on system installation and operation at LANL
- Complete apparatus will be shipped from US to J-Village (site of final preparations)
- System will be installed and operated at FD by TEPCO with LANL assistance
- Data collection and remote operations via wireless connection, and transmission of data to LANL computers in US. LANL scientists do not have to be at FD during measurement
- Data analysis performed in US by LANL team
- Decontamination and removal of system from FD will be done by TEPCO


Test can be deployed quickly in container.

■ Radiation

- Shield thickness
- Radiation safety
- Detectors (singles rate)
- Electronics

■ Demonstrate Solution


- Remote operation
- Remote Data Collection
- Tracking efficiency as function of shield thickness



Specific risk reductions can be anticipated.

- **Risks: \$, ¥, delays, operations, impaired measurement**
 - Unanticipated problems ALWAYS arise
- **Shielding study**
 - Optimize shielding design for the full imaging measurement
- **Wireless data collection**
 - Show wireless and GPS systems can operate in FD site environment.
- **Electric power**
 - Operational data and experience guiding robust system design
- **Redundancy for avoiding system failure**
 - Select redundancy features
 - Exercise recovery mode
- **System installation and operations**
 - Designs and procedures minimize personnel radiation exposure associated with installation and operations.

Test occupies smaller space than full deployment – on both sides.



Muon scattering can provide best images of reactor fuel.

- **Thick targets imaged inside very thick concrete shield**
 - 2.7-m of concrete – similar to Boiling Water Reactor (BWR)
 - 80-cm of Pb – similar to areal-density thickness of reactor fuel
 - ~ months to image each target
- **Scale-up to reactor**
 - Detectors would be at building exterior, ~50 m apart
 - Maintain ~ same solid angle with detectors 5-m x 10-m (commercially available)
 - Measure image showing location of fuel
 - Reactor “view” depends on location of detectors
 - Similar to LANL demonstration – view of reactor pressure vessel (RPV)
 - Installed below ground – view of lower reactor containment

LANL, US DOE, and CC2 funds have supported our work.

■ LANL funding

- Demonstration measurement – completed (September, 2011)
- TEPCO-LANL workshop
- Small reactor imaging

■ DOE funding for

- Japan-US Workshop, Washington, DC, 15-16 February, 2012
- Japan-US Workshop, KEK, Japan, 23-25 May, 2012

■ CC2 Investor funds

- TEPCO-LANL workshop
- Proposal preparation

■ Need TEPCO/METI funding for:

- Engineering and operations tests at Fukushima reactor
- Engineering studies of shielding, support, installation, operations, etc.
- Image cores of Fukushima reactors