LA-UR-20-30148

Approved for public release; distribution is unlimited.

Title: TWF Waste Container Receipt, Inspection and Transfer to Storage

Author(s): Grant, Robert Curtis Lucas

Intended for: Source document for NA-50 end to end review of Triad TRU waste operations

Issued: 2020-12-10

Disclaimer:

Los Alamos National Laboratory, an affirmative action/equal opportunity employer, is operated by Triad National Security, LLC for the National Nuclear Security Administration of U.S. Department of Energy under contract 89233218CNA000001. By approving this article, the publisher recognizes that the U.S. Government retains nonexclusive, royalty-free license to publish or reproduce the published form of this contribution, or to allow others to do so, for U.S. Government purposes. Los Alamos National Laboratory requests that the publisher identify this article as work performed under the auspices of the U.S. Department of Energy. Los Alamos National Laboratory strongly supports academic freedom and a researcher's right to publish; as an institution, however, the Laboratory does not endorse the viewpoint of a publication or guarantee its technical correctness.

Attachment A, IPC Cover Page

SECTION 1 - GENERAL PROCEDURE DETAILS (To be completed by DCC and Originator)					
☒ Permanent IPC		Effective Date: 06/24/2020			
OR					
☐ Temporary IPC		Expiration Date (Temp IPC only):			
DAR No.: 16150	Document No.: PA-DOP-01950			Revision(include IPC#): 1-IPC1	
Title: TWF Waste Container Receipt, Inspection and Transfer to Storage					
Print DCC Name/Z#:	Melissa M. Hobdy Smith/342720			DCC Phone:	665-1209
SECTION 2 - JUSTIFICATION OF NEED FOR IPC (To be completed by Originator and RLM)					
Print Originator Name/Z#:		Genevieve S. Aguilar Fernandez		Organization:	NPI-7
				Phone:	664-0108
Justification for requested change (Attach additional sheets if needed. Specify number of additional sheets: _____)					
TSR update needed to Attachment C.					
Does the IPC change to this procedure create, modify, move, or store a waste? ..... ☒ Yes ☐ No					
NOTE: If Yes, TRU Waste Review is required. TRU Waste Review, <u>NPI-7</u> and <u>EPC-CP</u> boxes must be checked in Section 4 below					
Changes occur on the following pages: 1, 2, 67					
Print RLM Name/Z#:		Nestor A. Trujillo/117869		RLM concurrence signature:	Date
				Nestor Trujillo	06/23/2020
Digitally signed by Nestor Trujillo Date: 2020.06.23 09:17:38 -06'00'					
SECTION 3 - DERIVATIVE CLASSIFICATION REVIEW (To be completed by DC/RO)					
NOTE: This review shall encompass the cover IPC and the procedure as one document.					
☒ Unclassified		☐ CONFIDENTIAL		☐ SECRET	
☐ Export Controlled Information		☐ Restricted Data			
☐ Official Use Only		☐ Formerly Restricted Data			
☐ Unclassified Controlled Nuclear Information		☐ National Security Information			
☐ Guidance Used: N/A		☐ Guidance Used:			
DC/RO Print Name/Z#:		Organization:		Signature:	Date:
Edward Cagle 198758		NPI-7		Edward Cagle	6/22/2020
Digitally signed by Edward Cagle Date: 2020.06.22 15:22:15 -06'00'					
SECTION 4 - RLM AND FOD APPOINTMENT OF DISCIPLINE REVIEWERS					
(To be completed by FOD AND RLM. Originator is responsible for ensuring reviews are completed Attach additional sheets if necessary.)					
Discipline (FOD and RLM)		Print Name/Z#		Signature	Date
TRU Waste Review	☒ NPI-7	Robert Grant/277220		Signature On File (Approved via email)	6/23/20
	☒ EPC-CP	Michael Furman/349992		Michael Furman	6/22/20
		Thomas Viail/236382		Signature On File (Approved via email)	6/23/20
SECTION 5 - SAFETY BASIS EVALUATION IF APPLICABLE (To be completed by QEV or DCC)					
Required USQ Evaluation:		☐ TA-55	☐ RLW	☐ CMR	☒ TWF
		☐ WCRRF	☐ RANT	☐ N/A	
USQ or Tracking Number (s) TWF-20-0923-S, R0				Andrea L. Tallbrother	Date: 2020.06.24 09:06:45 -06'00'
				Justification for N/A	
SECTION 6 - FINAL APPROVALS & ISSUANCE CONDITIONS (Signature indicates approval of IPC)					
(Indicate whether the document can be made effective and specify the effective date, if applicable)					
☐ Coordinate issuance with Operations Center ☒ Issue Upon Completion of QEV evaluation					
☐ Issue with Effective Date: _____					
Print RLM Name/Z#:		Org.:		Signature:	Date:
Nestor A. Trujillo		NPI-7		Nestor Trujillo	6/23/20
				Digitally signed by Nestor Trujillo Date: 2020.06.23 09:17:59 -06'00'	
Print FOD or designee Name/Z#:		Org.:		Signature:	Date:
Carlos Valdez		TA-55 WF		CARLOS VALDEZ (Affiliate)	6/23/20
				Digitally signed by CARLOS VALDEZ (Affiliate) Date: 2020.06.23 11:20:36 -06'00'	

TA-63/TWF

Detailed Operating Procedure

Approval Cover Sheet

Document Number: PA-DOP-01950, R1-IPC1
Effective Date: 06/18/2020
Next Review Date: 06/18/2022
Supersedes: TWF-WO-DOP-3000, R15-IPC4

Title: TWF Waste Container Receipt, Inspection and Transfer to Storage

Status:

- ☒ New
☐ Major revision
☐ Minor revision

Hazard:

- ☐ Low-hazard
☒ Moderate-hazard
☐ High-hazard/complex

For Document Control Use Only:**Use Type:**

- ☒ Reference ☒ Use Every Time (All Attachments)
☐ Reader-Worker

Document Preparer/SME:

Robert Grant

Organization

NPI-7

Signature/Date**Approved for Use By:**

Nestor Trujillo

NPI-7

RLM

Approved for Use By:

FOD

Carlos Valdez

TA55-WF

TWF Operations Manager

Derivative Classification Review

- ☐ UNCLASSIFIED
☐ Export Controlled Information
☐ Official Use Only
☐ Unclassified Controlled Nuclear Information

- ☐ CONFIDENTIAL ☐ SECRET
☐ Restricted Data
☐ Formerly Restricted Data
☐ National Security Information

Guidance Used:

Guidance Used:

DC/RO Name/Title/Z Number:

Organization:

Signature:

Date:

Revision History

Document Number	Effective	Action	Description
<u>PA-DOP-01950, R1- IPC1</u>	<u>06/24/2020</u>	<u>IPC</u>	• <u>Revised Attachment C to reflect latest TSR.</u>
PA-DOP-01950, R0	<u>06/18/20</u>	New Document	• Supersedes TWF-WO-DOP-3000.

PA-DOP-01950, R1-IPC1, GAF 6/22/20

Table of Contents

1.0	INTRODUCTION	4
1.1	Purpose	4
1.2	Scope	4
1.3	Applicability	4
1.4	Technical Safety Requirements (TSRs)	4
2.0	PRECAUTIONS AND LIMITATIONS	5
2.1	General	5
2.2	Additional Requirements and Conditions	11
3.0	PREREQUISITE ACTIONS	11
3.1	Planning and Coordination	11
3.2	Performance Documents	14
3.3	Special Tools, Equipment, Parts, and Supplies	14
3.4	Field Preparation	15
3.5	Approvals and Notifications	15
4.0	ACCEPTANCE CRITERIA	15
5.0	PERFORMANCE	1817
5.1	Receipt of Waste Containers	1817
5.2	Inspection of Waste Containers	3029
5.3	Transfer and Storage of Waste Containers	3234
5.4	Contingencies	3837
6.0	POST-PERFORMANCE ACTIVITIES	3938
6.1	Post Job Review	3938
6.2	Restoration	3938
6.3	Results	3938
6.4	Verification/Independent Verification	3938
7.0	DEFINITIONS AND ACRONYMS	3938
7.1	Definitions	3938
7.2	Acronyms	4039
8.0	RESPONSIBILITIES	4140
8.1	Operations Center Operator	4140
8.2	Shift Operations Manager	4140
8.3	Shift Operations Supervisor	4140
8.4	Waste Handler Operator	4140
8.5	Cognizant System Engineer	4140
8.6	Person In Charge	4140
9.0	REFERENCES	4241
10.0	RECORDS	4342
11.0	APPENDICES AND ATTACHMENTS	4443
	Appendix 1, WIPP Approved Vent Filters	4544
	Appendix 2, TRU Waste Metal Container Integrity Checklist	4645
	Attachment A, TWF Waste Container MAR Verification	5655
	Attachment B, TWF TRU Waste Container Metal/Type A Inspection	6564
	Attachment C, TWF Site and Shipping & Receiving Area MAR Verification	6766
	Attachment D, TWF Fueled Vehicle Inspection	7069
	Attachment E, TWF Waste Container Receipt Data Sheet	7271
	Attachment F, MAR Limit for WSBs	7675
	Attachment G, MAR Limit for the CWSB	7877
	Attachment H, Task ID Recording	8079
	Attachment I, Criticality Safety Verifications	8281
	Attachment J, Pre-Shipment Verifications	8483

1.0 INTRODUCTION

1.1 Purpose

This procedure provides instructions for the receipt, inspection, and transfer to storage of Transuranic (TRU) Waste Containers and Pipe Overpack Containers (POC) within the Transuranic Waste Facility (TWF) (Waste Storage Buildings [WSBs] and Characterization and Waste Storage Building [CWSB]). Performance of this procedure meets the requirements of AC 5.8.9, AC 5.8.13 2nd Bullet, SAC 5.9.1, SAC 5.9.3, SR 4.2.1.1, 4.2.1.2, 4.2.1.5, 4.2.1.6, 4.2.2.1, 4.2.2.2, 4.2.2.3, 4.2.2.4, 4.2.3.1, 4.2.3.2, 4.2.3.3, 4.3.4.1, 4.4.1.1, 4.4.1.2 and 4.4.1.3.

1.2 Scope

The procedure is used for the following:

- Receipt and inspection of TRU Waste Containers / POCs into the Shipping and Receiving Area.
- Transfer of TRU Waste Containers / POCs, which include the handling (sorting, staging, palletizing, banding, etc.) of waste containers, from the Shipping and Receiving Area to the initial storage destination (WSBs and/or CWSB).
- Ensuring the TA-63 TWF required hazardous waste container storage criterion are met prior to transfer and meet the physical storage requirements for placement at the permitted units (WSBs and/or CWSB) upon arrival.

Receipt and transfer activities described within this procedure are performed using the Waste Compliance and Tracking System (WCATS) to verify that all possible Technical Safety Requirements (TSRs) material at risk (MAR) inventory limits are met prior to transfer.

This procedure SHALL be performed in OPERATION MODE.

1.3 Applicability

This procedure applies to the receipt, inspection, and transfer to storage of TRU Waste Containers.

1.4 Technical Safety Requirements (TSRs)

NOTE Performance steps that are important to TSR implementation are denoted by a dollar sign (\$). Procedure steps marked with the (\$) symbol implement key requirements associated with the facility's safety basis. These steps may not be changed without approval to ensure that the TSRs and other associated requirements are maintained.

The requirements of the following Administrative Control (AC), Specific Administrative Control (SAC) and Surveillance Requirements (SR)/ are verified during the performance of this procedure:

1.4 Technical Safety Requirements (TSRs) (continued)

AC 5.8.9

AC 5.8.13 2nd Bullet

SAC 5.9.1

SAC 5.9.3

SR 4.2.1.1

SR 4.2.1.2

SR 4.2.1.5

SR 4.2.1.6

SR 4.2.2.1

SR 4.2.2.2

SR 4.2.2.3

SR 4.2.2.4

SR 4.2.3.1

SR 4.2.3.2

SR 4.2.3.3

SR 4.3.4.1

SR 4.4.1.1

SR 4.4.1.2

SR 4.4.1.3

2.0 PRECAUTIONS AND LIMITATIONS

2.1 General

A. Pause/Stop Work

All workers are responsible for pausing or stopping work when they have a reasonable belief that quality, work risks or hazards are not effectively controlled and workers have the right to do so without fear of reprisal. LANL policy P101-18, *Procedure for Pause/Stop Work*, provides more information on the differences between pausing or stopping work and the process for resuming work in either case.

If this procedure cannot be completed as written or abnormal conditions are encountered, PAUSE, place the work in a safe configuration if possible, and notify the Operations Center (OC) and first line manager (FLM).

2.1 General (continued)

B. Hazards and Controls

Hazards	Controls
Radiation Exposure	• All postings must be obeyed. • All radiological control technician (RCT) verbal directions must be followed. • As Low as Reasonably Achievable (ALARA) guidelines must be followed. • Personnel shall wear appropriate dosimetry (thermoluminescent dosimeters [TLDs], wrist dosimeters) per radiological work postings (RWPs), postings, and dosimetry enrollment. • RWP instructions must be followed if an RWP is in place.
Pinch points and sharp edges	• Any skin injuries (abrasions, cuts, or blisters) obtained while handling waste containers are to be reported to the RCT and TWF Operations Center. • Workers must be aware of pinch point areas. • Leather gloves must be worn when handling waste containers. • The worker must ensure their body is well centered and balanced prior to manipulating containers. • Both hands should be used whenever possible. • Awkward positions are to be avoided.
Ergonomics - body stresses	• Mechanical aids (e.g., carts, dollies) are to be used to avoid lifting objects weighing more than 75 lbs. once per day, 55 lbs. more than 10 times per day. • Workers should avoid repeating awkward positions for more than 2 hours (combined total) per day.
Noise	• Controls posted in work areas for noise exposure at or above the Occupational Exposure Limits (OELs) must be followed. • Hearing protection must be worn in the WSBs/CWSB when forklifts are operating.
Emergency Events (e.g., Fire, Explosion, breached container, injured person)	• Workers must pause work, warn others, isolate the immediate area. • Workers must evacuate to an Assembly/Muster area upwind of the incident. • Notifications must be made (911, Ops Center).

2.1 General (continued)**B. Hazards and Controls (continued)**

Hazards	Controls
Abnormal Events: Discovery of a Liquid or Solid Material release or spill, unplanned loss of electrical power, waste container of questionable integrity, Criticality Safety Non- compliance	- Workers must pause work, warn others, isolate the immediate area. - Workers must move away, upwind of the event. - Notifications must be made (Operations Center, Shift Operations Supervisor [SOS]).
Nuclear Criticality Accident	- There are four interrelated elements of the TA-55 Criticality Safety Program that protect against a nuclear criticality accident: - Written operating procedures and process descriptions, - Nuclear Criticality Safety requirements, developed from the process descriptions, that constrain the operating parameters within acceptable limits, - A formality of operations program that ensures compliance to procedures requirements; and, - Operator training. - Operators must comply with the criticality safety posting requirements (e.g., mass, form, volume, containerization, etc.) throughout the execution of the procedure. - Refer to section 2.1E, Criticality Safety Requirements for process-specific criticality safety requirements.
Severe Weather	- Flooding: Workers shall pause work and take shelter when flooding threatens personnel or equipment safety. - Rain, snow or hail storms: Workers shall pause work and take shelter when rain, snow or hail storms threaten personnel or equipment safety. - Winds: High winds: Workers shall pause work and take shelter. - Lightning: Workers shall pause work and take shelter when time between lightning flash and thunder is 30 seconds or less. Work may be resumed after waiting 30 minutes after the intervals exceed 30 seconds.

2.1 General (continued)

B. Hazards and Controls (continued)

Hazards	Controls
Slips, Trips and Falls	- Workers should be observant and use caution when moving around area. - Workers must be aware of the swale in the shipping and receiving area. - Snow or icy surfaces shall be avoided. - Good housekeeping shall be maintained. - Workers must stay on designated pathways. - Workers must maintain eyes on path and maintain awareness of potential hazards around path. - Workers must be aware of uneven floors, beams, pipes, curbs, fixed equipment, hoses and electrical cords.
Vehicle and Pedestrian Safety	- Workers must watch for trucks and forklifts on roadways. - Speed limit is ≤ 10 mph and is posted.
Thermal Stress Cold or Hot	- Workers must stay hydrated. - Sheltered breaks shall be taken as necessary to warm up or cool down. - Sunscreen must be used as necessary. - Workers must dress appropriately for the weather.
Stacking of containers 3 high: High Consequence Material Handling Activity	- Form 2041, <i>High-Consequence Material Handling Activity</i>, must be completed. - The requirements of P101-4, <i>Forklifts and Powered Industrial Trucks</i> must be followed. - Third tier stacking forklift operations shall be performed in accordance with TWF-FO-DOP-2003, <i>TWF/RANT Forklift Operations</i>.
Working with Forklifts: Contact with building, protrusions or Electrical lines, tip-over of or falls from forklift, Loss of all or part of load	- Only trained and authorized personnel may operate forklifts. - The forklift must be inspected prior to use. - The work area must be inspected for hazards against maneuvering forklift. - A Spotter shall be used when obstructions are present. - Spotters and other personnel shall not stand under rollup doors. - Hearing protection is required for personnel in the WSBs/CWSB when forklifts are present and operating.
Working with Forklifts: An item on a pallet slips, tips over, or falls while being moved	NOTE As used here, an item is any object moved by NPI-7 on a pallet whether empty or not. - When moving an item or items on a pallet, the load must be secured. - Workers must ensure the load is stable and balanced.

2.1 General (continued)

B. Hazards and Controls (continued)

Hazards	Controls
Fall Protection: Working from a ladder/or elevated work surfaces (e.g., back of the shipment trailer)	• Ensure fall protection equipment has a current inspection and is not damaged. • Set-up platform ladder at side door of trailer. • If work will be performed close to the edge of the loading/unloading area, set-up the safety-net. • A harness and 6 foot lanyard will be used if standing less than 6 foot from the trailer opening without the safety net.

C. Unique Entry Conditions

Not Applicable

D. Basis for Use Categorization/Sequence of Steps

This is a Reference procedure with the exception of the attachments, which are Use Every Time (UET). All the steps in the Performance section are to be performed in sequence unless otherwise stated.

The subsections and steps in the performance section are to be performed in sequence unless otherwise stated.

E. Criticality Safety Requirements

NOTE Performance steps that are important to criticality safety are denoted by a circle-CS symbol.

This is a facility-wide general use procedure that is utilized in a significant number of locations throughout the facility. The person in charge (PIC) and worker **shall** obtain and use the criticality safety posting to determine the specific requirements for each location involved in the planned operation.

NOTE 1 The criticality safety program is designated to protect personnel, the public, and the environment from the consequences of a criticality accident, preferably by prevention of accidents.

NOTE 2 Criticality Safety Posting TWF-CSP-1009, *TWF Waste Operations*, is posted at the WSBs/CWSB and lists the applicable criticality safety requirements from the CSEDs below.

NCS-CSED-16-014, *Criticality Safety Evaluation for the Transuranic Waste Facility at TA-63*

- Drums (55-gallons and larger, including pipe overpacks) ≤ 200 ²³⁹Pu Fissile Gram Equivalent (FGE) each

2.1 General (continued)

E. Criticality Safety Requirements (continued)

- Standard Waste Boxes (SWBs) (or larger containers) ≤ 325 ²³⁹Pu FGE each
- Stacked ≤ 3 containers high
- Containers shall not be opened
- 55 gallon (Type A) steel drums
- There is no limitation on the number of waste drums/containers, and they may be in contact and be commingled

NCS-CSED-14-133, *Criticality Safety Evaluation for Onsite Transfers of Fissile Waste Material*

- ≤ 75 containers per transfer vehicle
- Stacked ≤ 3 containers high
- If > 75 containers are present (e.g., in another transfer vehicle or a storage array), each transfer vehicle shall be separated by ≥ 10 feet from other arrays of waste containers.

F. Required Permits

LANL Hazardous Waste Facility Permit, Section 3.

G. Training and/or Qualification

Workers performing the waste handling tasks associated with this procedure must complete:

- *TWF Waste Operations Training* (Curriculum # 5952)
- *WQ TA-55 Forklift Operator & Proficiency* (Curriculum # 12348)
- *Ladder Climbers* (Curriculum # 4257)

Workers must obtain authorization to conduct work from the responsible line manager (RLM) or the RLM Designee.

H. General Warnings and Cautions

WARNING

Items being moved on a pallet must be secured.

2.1 General (continued)

I. Nuclear Material Control and Accountability

The use of the Local Area Nuclear Material Accountability Software/Los Alamos Materials Control and Accountability System (LANMAS/LAMCAS) is required for all accountable special nuclear material (SNM)/nuclear material (NM) movement between Nuclear Material Control and Accountability (NMCA) locations or processing items for the purpose of altering weight or configuration.

Material holdings must comply with associated process monitoring flow diagrams (PMFDs). See TA55-RD-585, *Nuclear Materials Control and Accountability Requirements*, for additional guidance.

Applicable LANMAS/LAMCAS transactions must be completed within three hours of the operational event. If the NMCA transaction cannot be performed, e.g., system is non-functional, will not accept transaction, etc., contact the account custodian, hardened room, or go to the hardened room for assistance.

2.2 Additional Requirements and Conditions

Not Applicable

3.0 PREREQUISITE ACTIONS

The sections and the steps in this section are not required to be performed in sequence, unless otherwise stated.

3.1 Planning and Coordination

NOTE Procedure steps marked with the (&) symbol implement key requirements associated with the Resource Conservation and Recovery Act (RCRA) or other environmental regulatory requirements. These steps may not be changed without Environmental Compliance (Environmental Protection and Compliance Division, Waste Management Programs Group [EPC-WMP]) approval to ensure LANL Hazardous Waste Facility Permit requirements and other environmental regulatory requirements are met.

Shift Operations Manager (SOM) or Designee

- Ensure this procedure is the latest revision and identify this procedure as “WORKING COPY” on the title page.
  - IF there are no POCs or TRU Waste Containers within the shipment, THEN enter N/A on Attachment J, *Pre-Shipment Verifications*, where applicable.

3.1 Planning and Coordination (continued)

- Perform the following prior to allowing the shipment to leave for TWF, documenting on the applicable attachment:
  - Obtain and verify the following transfer paperwork on Attachment J:
    - Shipment or Transfer Pickup Report from WCATS (desktop application)
    - Transuranic Waste Storage Record (TWSR) (from WCATS)
    - Type 7A Container Documentation for Drums and POCs (from NPI-7)
  - CS ○ Verify there are ≤ 75 (waste) containers in the Shipping Trailer (transfer vehicle) by reviewing the Pickup Report (Attachment I, *Criticality Safety Verifications*).
  - CS ○ If > 75 containers are present (e.g., in another transfer vehicle or a storage array), ensure each transfer vehicle is separated by > 10 feet from other arrays of waste containers.
  - \$ ○ Ensure no TRU waste containers within this shipment is greater than 200 mr/hr on contact (neutron + beta/gamma) (Attachment J).

NOTE The LANL waste acceptance into TWF needs to abide by the most restrictive date in either the TWF Document Safety Analysis or LANL Hazardous Waste Facility Permit.

- & ○ Ensure no mixed waste generated prior to April 21, 2011 is within this shipment using the accumulation start date found in the WCATS Desktop Application. (**Ref. NM Hazardous Waste Bureau Memo May 17, 2018**) (Attachment J)
- \$ ○ Ensure only newly generated waste (December 31, 1998 and later) and no legacy waste (before December 31, 1998) are within this shipment (using the closure date from the TWSR found in the WCATS Desktop Application). (**AC 5.8.9**) (**SR 4.2.3.1**) (**Ref. DOE Memo June 29, 1998**) (Attachment J)
- \$ ○ IF there are POC(s) within this shipment, THEN verify the following by utilizing WCATS –TWSR (container type) or from information obtained from NPI-7. (Attachment J) (**SR 4.4.1.2**)
  - POC meets the criteria specified in Specification for Fabrication of Pipe Overpack (Standard, S100, S200, and S300 per POC-SPC-0001).
  - The vent filter on the POC outer container is an UltraTech 9424S filter

3.1 Planning and Coordination (continued)

- § ○ Verify each container's Waste Stream Profile is active (current) by utilizing the WCATS Desktop Application (**SR 4.2.3.3**) (Attachment J)
- § ○ Ensure no D001, D002, D003 coded waste or PCBs are within this shipment by utilizing WCATS desktop application. (**SR 4.2.3.2**) (Attachment J)
- Ensure every container on the shipment contains $\leq 1.0\%$ Beryllium (from NPI-7). (Attachment J)
- & ○ Ensure no waste containers with greater than 1% free liquid, as defined in 40 CFR 260.10, *Hazardous Waste Management System: General: Definitions*, are within this shipment by utilizing WCATS desktop application. (Attachment J)
- Ensure every container on the shipment is TRU Waste (>100 nCi/g) utilizing WCATS desktop application. (Attachment J)
- CS ○ Verify there are no High ^{239}Pu Fissile Gram Equivalent (FGE) (drums/ pipe overpacks > 200 FGE and SWBs > 325 FGE) containers within this shipment, by utilizing WCATS "Pu-239 FGE [2U]". (**Ref. E-Mail 04/27/2017, Criticality Safety Comment**) (Attachment I)

NOTE The Technical Supervisor review and the TWF Waste Management review verify that the Waste Stream Profile ID is correct for each container, which links the waste to institutional review of the Waste Stream ID and the relevant AK report. Facilities Operations Director (FOD) testing per LA-UR-18-23024, *Oxidizer Test Results for Cheesecloth (Cellulose) Exposed to 12.0 M Nitric Acid*, demonstrates there are no concerns for oxidation chemicals in the waste stream profiles.

- Verify the Technical Supervisor (TS) review (TS-REV) is complete and approved for each container in the WCATS Desktop Application. (Attachment J)
- Verify TRU Waste Facility Management Review (TWFWM-REV) is complete and approved for each container in the WCATS Desktop Application. (Attachment J)
- Document completion of the pre-shipment verifications on Attachment J with printed name, signature, Z#, date, and time.
- Determine if waste contains Tritium (utilizing WCATS Desktop Application).
  - IF waste is determined to contain Tritium,
THEN notify RCTs.
- Ensure work is scheduled per P300, *Integrated Work Management*.

3.2 Performance Documents

- Shipment or Transfer Pickup Report from WCATS (desktop application)
- Transuranic Waste Storage Record (TWSR)
- Traveler (PT-WI-001), as applicable
- Uniform Hazardous Waste Manifest (EPA Form 8700-22), as applicable
- Radioactive Material Transfer Form (Form 1586) (as applicable)
- Waste Acceptance Criteria Exception Forms (Form 1973), as applicable
- TWF-CSP-1009, *TWF Waste Operations*
- TWF-FO-DOP-2003, *TWF/RANT Forklift Operations*
- TWF-WO-DOP-3007, *TWF Banding Activities*, as applicable
- Type 7A Container Documentation (from NPI-7)
- POC Documentation (from NPI-7), as applicable

3.3 Special Tools, Equipment, Parts, and Supplies

NOTE Where appropriate, equipment must have current periodic inspection before use.

- Fall protection (for the shipping trailer)
- Drum banding equipment and supplies (if applicable)
- Pallet jack (if applicable)
- Inspection tool for bottom of waste containers (e.g., mirror)
- WCATS mobile device
- Forklift
- Approved lifting devices
- Two-way radio
- Metal cart
- Rolling ladder
- Red ink pen (for marking any Unsatisfactory [UNSAT] conditions)
- Highlighter(s)
- Empty pallets (the number will depend on how many waste containers are being received)
- ML3 ratchet straps

3.4 Field Preparation

- [1] Ensure that the specified tools, equipment, and materials listed in Section 3.3 are available in the work area.

3.5 Approvals and Notifications

- [1] Obtain permission from the TWF SOM or Designee to perform the following:
- Waste container receipts at TWF
- [2] Obtain permission from the TWF Operations Center to perform the following:
- Permission to perform this procedure.
  - Waste Container transfers to their identified storage destination (WSBs and/or CWSB)
  - Contact TWF Nuclear Material Control and Accountability (NMCA) custodian prior to movement of TRU waste.

4.0 ACCEPTANCE CRITERIA

- § AC 5.8.9 Only newly generated waste and NO legacy waste is accepted at TWF.
- § AC 5.8.13 2nd Bullet When unsafe weather conditions (e.g., high wind, lightning, rain, snow) are observed or are known to be imminent pickup or receipt operations are terminated and containers are placed in a protected structure.
- § SAC 5.9.1 Except for POCs, a PAYLOAD SHALL be limited to one of the following configurations:
1. A maximum of four (4) drums
- OR
2. Only one (1) SWB/SLB2 (either an OVERPACKED SWB or a direct-loaded SWB/SLB2)
- § SAC 5.9.3 Fossil-fueled or bio-fueled vehicles, except for emergency vehicles during actual emergencies, SHALL not be present in the WASTE STORAGE AREA when MAR is present.
- § SR 4.2.1.1 VERIFY the MAR in the affected individual WSB is $\leq 2,720$ PE-Ci as waste. (Prior to the introduction of MAR into the affected WSB)
- § SR 4.2.1.2 VERIFY the MAR in the CWSB is $\leq 2,880$ PE-Ci as waste. (Prior to the introduction of MAR into the CWSB)
- § SR 4.2.1.5 VERIFY the MAR in the SHIPPING AND RECEIVING AREA is either $\leq 1,240$ PE-Ci as waste
- OR**
- ≤ 42 PE-Ci as SEALED SOURCES.
(Prior to acceptance of MAR into the SHIPPING AND RECEIVING AREA)

4.0 ACCEPTANCE CRITERIA (continued)

- § SR 4.2.1.6 VERIFY the TWF SITE MAR is $\leq 19,180$ PE-Ci as waste and ≤ 42 PE-Ci as SEALED SOURCES. (Prior to acceptance of MAR into the TWF SITE)
- § SR 4.2.2.1 Verify the MAR in each drum is ≤ 80 PE-Ci. (Prior to acceptance at the TWF SITE)
- § SR 4.2.2.2 VERIFY the MAR in each Direct-Loaded SWB/SLB2 is ≤ 300 PE-Ci. (Prior to acceptance at the TWF SITE)
- § SR 4.2.2.3 VERIFY the MAR in each OVERPACKED SWB is ≤ 1000 PE-Ci. (Prior to acceptance at the TWF SITE)
- § SR 4.2.2.4 VERIFY the MAR in each POC is $\leq 1,800$ PE-Ci. (Prior to acceptance at the TWF SITE)
- § SR 4.2.3.1 VERIFY that the TRU WASTE CONTAINER contains newly generated waste. (Prior to acceptance at the TWF SITE)
- § SR 4.2.3.2 ENSURE that the TRU WASTE CONTAINER has documentation that states there is no waste coded D001, D002, D003 or PCBs. (Prior to acceptance at the TWF SITE)
- § SR 4.2.3.3 ENSURE that the TRU WASTE CONTAINER has documentation of an active Waste Stream Profile. (Prior to acceptance at the TWF SITE)
- § SR 4.3.4.1 VERIFY the LCO is met. (Prior to performing MAR HANDLING OPERATIONS)
- LCO The following vehicles SHALL be prohibited in the TWF SITE, with the exception of 1) emergency vehicles during drill/exercise or actual emergency: 2) snow removal equipment: and 3) transportation vehicles within the scope of the transportation document:
- fossil-fueled vehicles
  - bio-fueled vehicles
  - vehicles capable of speeds >10 mph
  - fossil/bio-fueled transportation vehicles capable of speeds >10 mph during MAR HANDLING OPERATIONS
- § SR 4.4.1.1 VERIFY the TRU WASTE CONTAINER is metal and of a design whose prototype met the tests specified in 49 CFR 173.465, *Type A Packaging Tests*. (prior to accepting a non-POC TRU WASTE CONTAINER at the TWF SITE)
- § SR 4.4.1.2 VERIFY that the inner and outer containers of the Pipe Overpack Container are of a design that meets the criteria specified in Specification for Fabrication of the Pipe Overpack (Standard, S100, S200 and S300) (POC-SPC-0001), and VERIFY that the vent filter on the outer container is an UltraTech 9424S filter. (prior to accepting a Pipe Overpack Container containing MAR at the TWF SITE)

4.0 ACCEPTANCE CRITERIA (continued)

- § SR 4.4.1.3 VISUALLY inspect the outer TRU WASTE CONTAINER to be of sound integrity and VERIFY that a vent is installed on the outer container with no evidence of clogging. (prior to TRANSFER of a TRU WASTE CONTAINER to the WASTE STORAGE AREA)

5.0 PERFORMANCE

NOTE 1 Radiological surveys may be performed during this section at any time as deemed necessary by the RCT. Anytime radiological contamination is discovered, personnel will follow direction provided by the RCT.

NOTE 2 If external surveys show >5 mrem/hr at 30 cm, an RWP is required.

NOTE 3 The term “waste container” is used throughout the Performance section to generically describe all container types (TRU Waste Container, POC, SWB/Standard Large Box 2’s [SLB2s], Overpacked SWBs). If a specific type of waste container is applicable to an action, it will be spelled out by name and capitalized (i.e., TRU Waste Container, POC, SWB/SLB2, Overpacked SWBs).

[1] Ensure this procedure is the latest revision.

[a] Identify this procedure as “WORKING COPY” on the title page.

[2] Verify that TWF is in OPERATION MODE.

[a] IF TWF is NOT in OPERATION MODE,
THEN discontinue performance of this procedure and notify the
Operations Center.

[3] Verify work is released in accordance with P300 and has been approved for all tasks prior to performing them.

NOTE Inclement weather restrictions require terminating pickup or receipt operations and placing containers in a protected structure when unsafe weather conditions (e.g., high wind, lightning, rain, snow) are observed or are known to be imminent.

§ [4] Evaluate for inclement weather conditions (e.g., high wind, lightning, rain, snow, etc.). (**AC 5.8.13 2nd Bullet**)

[5] Ensure that a Pre-Job Brief is performed in accordance with TWF-FO-AP-2002, *TWF Pre-Job Briefings*.

5.1 Receipt of Waste Containers

PIC

[1] Ensure the following:

- Prerequisite actions in Section 3.0 are completed.
- Daily rounds are complete per PA-DOP-01939, *TWF Operations Round Sheet*.
- Per PA-DOP-01939, the Catenary Lightning Protection System inside the yard is satisfactory.

5.1 Receipt of Waste Containers (continued)

Waste Handler Operator

- [2] Using the WCATS Pick Up Report, ensure the following is recorded on the applicable attachments:
- [a] The Pickup Report number on all Attachments
  - [b] The following information, for each waste container within the shipment, on Attachment A, *TWF Waste Container MAR Verification*, and Attachment E, *TWF Waste Container Receipt Data Sheet*:
    - Waste Container Identification Number
    - Waste Container Configuration

- § [3] Using the WCATS Pick Up Report, verify none of the waste containers exceed the following criteria:
- MAR in each drum is ≤ 80 PE-Ci (**SR 4.2.2.1**)
  - MAR in each direct-loaded SWB/SLB2 is ≤ 300 PE-Ci (**SR 4.2.2.2**)
  - MAR in each OVERPACKED SWB is $\leq 1,000$ PE-Ci (**SR 4.2.2.3**)
  - MAR in each POC is ≤ 1800 PE-Ci (**SR 4.2.2.4**)

NOTE If this shipment does not contain TRU Waste Containers, POCs, direct loaded SWBs/SBL2s, or Overpacked SWBs, the applicable attachment section for SR 4.2.2.1, SR 4.2.2.2, SR 4.2.2.3 or SR 4.2.2.4 shall be marked N/A and the reason documented in the applicable COMMENTS section.

- [4] Circle SAT or UNSAT or N/A for each applicable container type within this shipment on Attachment A.
- [a] IF SAT is circled for all applicable container types (TRU Waste Containers, POCs, SWBs/SLB2 or Overpacked SWBs) THEN perform the following:
    1. Initial on Attachment A.
    2. Sign off on the COMPLETED BY section of Attachment A.
  - [b] IF UNSAT is circled for any of the applicable container types (drums, SWBs/SBL2 or Overpacked SWBs), THEN perform the following:
    1. Pause work.
    2. Notify the PIC and TWF Operations Center.
    3. Initial on Attachment A.

5.1 Receipt of Waste Containers (continued)

4. Document in COMMENTS sections of Attachment A.
5. Sign off on the COMPLETED BY section of Attachment A.
6. Wait for further instructions from the Operations Center.

[c] IF N/A is circled for any of the applicable container types (drums, SWBs/SBL2 or Overpacked SWBs),
THEN document the reason in the applicable COMMENTS section.

NOTE 1 The waste container Purchase Order number, Lot Number, and Serial Number may be obtained from the Payload Preparation section of the WCATS desktop application.

NOTE 2 Verification that the TRU Waste Container is metal and Type A is provided by NPI-7, Hazardous Material Management in an electronic or hard copy form.

NOTE 3 Anytime a Criticality Safety limit is exceeded TWF-FO-AP-2006, *TWF Nuclear Criticality Safety Administration*, section on Process Deviations must be implemented.

Ⓢ

[5] Verify, using the information provided by NPI-7, that all TRU Waste Containers within the shipment meet the following requirements:

- Container is metal (steel)
- Container is Type A

[6] Circle SAT or UNSAT on Attachment B, *TWF TRU Waste Container Metal/Type A Inspection. (SR 4.4.1.1)*

[a] IF SAT is circled,
THEN perform the following:

1. Initial on Attachment B.
2. Sign off on the COMPLETED BY section of Attachment B.
3. Initial/date on Attachment I.

[b] IF UNSAT is circled,
THEN perform the following:

1. Pause work.
2. Notify the PIC and TWF Operations Center.
3. Initial on Attachment B.

5.1 Receipt of Waste Containers (continued)

4. Document in COMMENTS sections of Attachment B and Attachment I.
5. Sign off on the COMPLETED BY section of Attachment B.
6. Wait for further instructions from the Operations Center.

[7] While the transportation truck and shipping trailer are connected and outside the TWF SITE, perform the following using the Pickup Report, WCATS mobile device and/or WCATS Desktop Application:

[a] Verify the following electronic signatures are present on 63-TWF-RECV-TRU:

- Originating Facility Operator
- DOT Reviewer
- Onsite TSDF Transporter

[b] Document on Attachment J with printed name, signature, Z#, date and time.

[c] Complete a WCATS INTER-FACILITY PICKUP to RECV-TRU.

NOTE Performing a Test Execute in WCATS will verify the MAR Surveillance Requirements.

[d] Record task date and time on Attachment H, *Task ID Recording*.

[e] Record Task ID on Attachment H.

[f] Print the WCATS Desktop displayed report.

NOTE The Surveillance Requirement restriction for Sealed Sources (SR 4.2.1.6) will remain in this procedure so as not to split the SR.

§ [g] Verify the following limits are not exceeded (**SR 4.2.1.5** and **4.2.1.6**):

- MAR in the SHIPPING AND RECEIVING AREA is either $\leq 1,240$ PE-Ci as waste
OR
 ≤ 42 PE-Ci as SEALED SOURCES. (**SR 4.2.1.5**)
- TWF SITE MAR is $\leq 19,180$ PE-Ci as waste, and ≤ 42.0 PE-Ci as SEALED SOURCES (**SR 4.2.1.6**)

[h] Document SAT or UNSAT on Attachment C, *TWF Site and Shipping & Receiving Area MAR Verification*. (**SR 4.2.1.5** and **SR 4.2.1.6**)

1. IF SAT is circled,
THEN perform the following:

5.1 Receipt of Waste Containers (continued)

- a. Initial on Attachment C.
    - b. Sign off on the COMPLETED BY section of Attachment C.
  2. IF UNSAT is circled,
THEN perform the following:
    - a. Pause work.
    - b. Notify the PIC and TWF Operations Center.
    - c. Initial on Attachment C.
    - d. Document in COMMENTS sections of Attachment C.
    - e. Sign off on the COMPLETED BY section of Attachment C.
    - f. Wait for further instructions from the Operations Center.
- [8] IF applicable,
THEN obtain and verify the Traveler (PT-WI-001) or Uniform Hazardous Waste Manifest (EPA Form 8700-22) (from driver).
- [9] Compare the waste container ID(s) on the Pickup Report with the waste container ID(s) on the drivers Traveler or Waste Manifest(s) if applicable.
  - [a] IF the waste container ID(s) on the Pickup Report match the waste container ID(s) on the drivers Traveler or Waste Manifest(s),
THEN sign the drivers Waste Manifest(s) if applicable.
  - [b] IF there is any discrepancy between the waste container ID(s) on the Pickup Report and the waste container ID(s) on the drivers Traveler or Waste Manifest(s),
THEN perform the following:
    1. Pause work.
    2. Notify the PIC and TWF Operations Center.
    3. Wait for further instructions.
- NOTE 1 The remaining steps may involve multiple shipping trailers so repeating steps for multiple trailers may be performed as required.
- NOTE 2 Anytime a Criticality Safety limit is exceeded TWF-FO-AP-2006, section on Process Deviations must be implemented.
- § [10] Verify there are no fossil-fueled vehicles, bio-fueled vehicles and/or vehicles capable of speeds >10 mph in the TWF Site. (SR 4.3.4.1)

5.1 Receipt of Waste Containers (continued)

- [a] Document SAT or UNSAT on Attachment D, *TWF Fueled Vehicle Inspection*.
- [b] IF SAT is circled,
THEN perform the following:
  - 1. Initial on Attachment D.
  - 2. Sign off on the COMPLETED BY section of Attachment D.
- [c] IF UNSAT is circled,
THEN perform the following:
  - 1. Pause work.
  - 2. Notify the PIC and TWF Operations Center.
  - 3. Initial on Attachment D.
  - 4. Document in COMMENTS sections of Attachment D.
  - 5. Sign off on the COMPLETED BY section of Attachment D.
  - 6. Wait for further instructions from the Operations Center.
- [11] Ensure all rollup doors on the WSBs and the CWSB are closed.
- [12] Obtain Operations Center permission to move the transportation truck(s) and shipping trailer(s) to the Shipping and Receiving area.
- [13] WHEN the transportation truck(s) and shipping trailer(s) is/are ready to be moved to the Shipping and Receiving Area,
THEN notify the driver(s) to perform the following:
  - [a] Move the transportation truck(s) and shipping trailer(s) to the Shipping and Receiving Area.
  - [b] Ensure the shipping trailer(s) wheels are chocked.
  - [c] Disconnect the transportation truck(s) from the shipping trailer(s).
  - [d] Ensure RCT performs a hand and foot survey of the driver(s) and spotter(s) prior to allowing re-entry to the transportation truck(s).
  - [e] Move the transportation truck(s) outside the TWF Site.
- [14] Open and secure the side and/or rear doors of the shipping trailer(s).
- [15] Before entering a shipping trailer, ensure a radiological (contamination) and dose rate survey of the shipping trailer(s) has been performed.

5.1 Receipt of Waste Containers (continued)

NOTE 1 Appendix 1, *WIPP Approved Vent Filters* provides guidance on approved filters.

NOTE 2 Any drum that does not have a vent filter installed and the plug is missing is considered an open waste container.

NOTE 3 The only Waste Isolation Pilot Plant (WIPP) approved vent filter for a POC is an UltraTech 9424S.

NOTE 4 Anytime a Criticality Safety limit is exceeded TWF-FO-AP-2006, section on Process Deviations must be implemented.

NOTE 5 Any drum that does not have a vent filter installed or the bung is open is considered an open waste container.

CS [16] While the waste containers are within the shipping trailer(s), verify the following Criticality Safety Limits:

- There is no open waste container within a shipping trailer (transfer vehicle).
- Waste containers are not stacked greater than 3 high.

[17] Initial/date on Attachment I.

[a] IF a waste container is found opened,
OR waste containers are stacked greater than 3 high within a shipping trailer,
THEN pause work and perform the following:

1. Exit the shipping trailer.
2. Close and secure the side and/or rear doors of the shipping trailer.
3. Notify the PIC and TWF Operations Center.
4. Annotate the deficient condition in the COMMENTS section on Attachment I.
5. Wait for further instructions from the Operations Center.

[18] Verify all waste containers within a shipping trailer match the following information from the Pickup Report:

- Waste Container Identification Number
- Waste Container configuration

5.1 Receipt of Waste Containers (continued)

[a] IF ANY waste container does NOT match the Pickup Report,
THEN perform the following:

1. Pause work.
2. Notify the PIC and TWF Operations Center.
3. Wait for further instructions from the Operations Center.

[19] Lift an approved lifting device onto the shipping trailer using proper lifting technique, if necessary.

[20] Ensure that any devices securing (e.g., ratchet straps) the waste containers have been removed from the waste containers.

[21] Spread out the waste containers as necessary.

NOTE Steps 5.1[22] through 5.1[30] may be performed out of sequence and simultaneously for each waste container.

§ [22] Verify that no D001, D002, D003 coded waste or PCB labeled waste is within this shipment and check (✓) YES or NO as applicable on Attachment E. **(SR 4.2.3.2)**

[a] IF YES is checked,
THEN perform the following:

1. Pause work and discontinue receipt of shipment.
2. Notify the TWF Operations Center there is a waste container that has either a D001, D002 or D003 code issue or PCBs within this shipment.
3. Wait for further instructions from the Operations Center.

§ [23] IF spacing within the shipping trailer allows,
THEN perform a waste container integrity inspection in accordance with section 5.2, using Attachment E for each waste container, ensuring that RCT performs (contamination) surveys as required. **(SR 4.4.1.3)**

§ [24] IF an integrity inspection was NOT performed or completed while the waste containers were within a shipping trailer,
THEN perform the following:

- [a] Go to Section 5.2, *Inspection of Waste Containers*.
- [b] Perform Attachment E for each waste container.

[25] Initiate a WCATS INTRA-FACILITY TRANSFER from RECV-TRU to SHIPSTAGE.

5.1 Receipt of Waste Containers (continued)

[26] Using the WCATS Mobile Device, scan/input all the waste containers.

WARNING 1

Risk of personal injury from a dropped load. At no time is any individual permitted to place any portion of the body under a suspended load.

WARNING 2

Risk of personal injury from manually moving a container that is beyond an individual's physical capabilities. Proper lifting techniques and the buddy system are to be employed when performing heavy lifting or movements in order to prevent personnel injuries. An approved lifting device should be used to manipulate drums inside the shipping trailer to an area where the drums can be reached with a drum grabber in order to prevent personnel injuries.

WARNING 3

Hazard of increased radiation dose from lingering near waste containers. ALARA guidelines are to be practiced while working around waste containers.

NOTE 1 The PIC, or designee, determines the order in which waste containers are removed from the shipping trailer(s).

NOTE 2 When removing waste containers from the shipping trailer(s) to the shipping and receiving area, TRU waste containers are not to be stacked greater than 3 high (on metal pallets).

NOTE 3 Anytime a Criticality Safety limit is exceeded TWF-FO-AP-2006, section on Process Deviations must be implemented.

CS

[27] Verify during the unloading of the waste container to the Shipping and Receiving Area that no waste containers were stacked greater than 3 containers high, and SHALL be palletized and each layer shall be bound together (LANL Permit 3.5.1(2)).

[28] Initial/Date on Attachment I.

[a] IF waste containers were stacked greater than 3 high within the Shipping and Receiving Area
THEN pause work and perform the following:

1. Notify the PIC and TWF Operations Center.
2. Annotate the deficient condition in the COMMENTS section on Attachment I.
3. Wait for further instructions.

5.1 Receipt of Waste Containers (continued)

- [29] Remove waste containers from the shipping trailer(s) using the following applicable method using appropriate unloading methods, including, but not limited to:
- Using a drum grabber for drums
  - Using a forklift with appropriate attachment for SWBs
- [30] Place the waste containers at an RCT designated location for further radiological (contamination and dose rate) surveying.

§

- [31] IF all waste containers have been inspected,
AND all are satisfactory (SAT),
THEN perform the following:
- [a] Circle SAT on Attachment E.
  - [b] Initial on Attachment E.
  - [c] Document in COMMENTS section of Attachment E.
  - [d] Sign off on the COMPLETED BY section of Attachment E.
- [32] IF any waste container is found to be unsatisfactory (UNSAT),
THEN perform the following:
- [a] Circle UNSAT on Attachment E.
  - [b] Initial on Attachment E.
  - [c] Document in COMMENTS section of Attachment E.
  - [d] Sign off on the COMPLETED BY section of Attachment E.

NOTE All communications concerning a waste container should include the WCATS Task Identification Number to ensure that all individuals communicating are referring to the same waste container.

- [33] Sign off on the Intra-Facility Transfer.
- [34] Record Task date and time on Attachment H.
- [35] Record Task ID on Attachment H.
- [36] Notify the TWF Operations Center that all of the waste containers have been accepted into the TWF Shipping and Receiving Area.
- [37] Ensure the “transfer” report is printed using the WCATS Desktop Application for documentation of transaction and file for records retention.

5.1 Receipt of Waste Containers (continued)

- [38] Ensure an RCT surveys the shipping trailer before the shipping vehicle leaves the facility.
- [a] IF radiological contamination is detected,
THEN perform the following:
1. Follow the RCT instructions.
  2. Notify the TWF Operations Center, SOS, and SOM for guidance and direction.
- [39] Ensure that the doors of the Shipping Trailer are closed and latched.

5.1 Receipt of Waste Containers (continued)

WARNING 1

§

Handling of TRU WASTE containers with a forklift presents several hazards: container breach, dropped containers, obstructed areas, inclines, and uneven surfaces. Forklift Operators SHALL determine the path of travel and be aware of the surroundings before handling TRU WASTE containers. Forklift operators must exercise extreme caution when handling elevated loads to ensure the immediate area is clear of personnel.

WARNING 2

Risk of personal injury from a dropped load. Workers must not attempt to stop a falling load and personnel in the immediate area must remain a safe distance from loads when loading or unloading containers from elevated position or stack.

WARNING 3

Increased radiation dose rate from lingering near waste containers. ALARA guidelines are to be practiced while working around waste containers.

NOTE 1 Waste container may be temporarily placed to regroup containers in order to obtain the identified containers for movement. Temporary placement for the purpose of accessing containers does not require securing the container to the forklift.

NOTE 2 In accordance with SAC 5.9.1 - Except for POCs, a PAYLOAD SHALL be limited to one of the following configurations:

- A maximum of four (4) drums (TRU Waste Containers)
- Only one (1) SWB/SLB2 (either an OVERPACKED SWB or a direct-loaded SWB/SLB2) (**SAC 5.9.1**)

NOTE 3 In accordance with SAC 5.9.1 Basis - there are no restrictions associated with POCs in a payload.

[40] Ensure the TRU Waste Containers are batched in the Shipping and Receiving area in accordance with the destination storage building and within the following restrictions:

- §
- A maximum of four (4) drums (TRU Waste Containers) on a single pallet (**SAC 5.9.1**)
- §
- Only one (1) SWB/SLB2 (either an OVERPACKED SWB or a direct-loaded SWB/SLB2) on a single pallet (**SAC 5.9.1**)
  - A maximum of four (4) POCs on a single pallet

5.1 Receipt of Waste Containers (continued)

NOTE Securing of a payload is required prior to movement.

- [41] IF banding is required,
THEN refer to TWF-WO-DOP-3007.
- [42] WHEN ready to transfer waste containers to storage,
THEN go to Section 5.3, *Transfer and Storage of Waste Containers*.

5.2 Inspection of Waste Containers

Waste Handler Operator

- NOTE 1** This section may be performed multiple times for the inspection of all waste containers within the shipment.
- NOTE 2** The steps in this section may be performed in any order and steps may be omitted during the integrity inspection performed inside the shipping trailer. ALL steps must be performed before each waste container is determined to be SAT/UNSAT.
- NOTE 3** Appendix 2, *TRU Waste Metal Containers Integrity Checklist* lists the criteria used for determining whether a TRU Waste Container is of sound integrity.
- NOTE 4** Appendix 1, *WIPP Approved Vent Filters* provides guidance on approved vent filters.
- [1] Verify RCT has performed a (contamination) survey of the bottoms of all TRU Waste Containers.
- § [2] IF TRU Waste Containers are within this shipment,
THEN determine whether the installed, WIPP approved, vent filter on the TRU Waste Container shows any evidence of being clogged, checking (✓) YES or NO for any evidence of a clogged WIPP-approved vent filter on Attachment E. **(SR 4.4.1.3)**
- [a] IF YES is checked,
THEN perform the following:
1. Pause work and discontinue receipt of shipment.
  2. Notify the PIC and TWF Operations Center there is a TRU Waste Container with a vent filter issue.
  3. Check UNSAT for the TRU Waste Container in question.
  4. Go to Step 5.1[34].

5.2 Inspection of Waste Containers (continued)

§ [3] IF POCs are within this shipment,
THEN determine whether the installed, WIPP approved, UltraTech 9424S vent filter on the POC outer container shows any evidence of being clogged, checking (√) YES or NO for any evidence of a clogged WIPP-approved UltraTech 9424S vent filter on Attachment E. (LCO 3.4.1.2)

[a] IF YES is checked,
THEN perform the following:

1. Pause work and discontinue receipt of shipment.
2. Notify the PIC and TWF Operations Center there is a POC with a vent filter issue.
3. Check UNSAT for the POC in question.
4. Go to Step 5.1[34].

NOTE 1 Appendix 2, *TRU Waste Metal Containers Integrity Checklist* lists the criteria used for determining whether a TRU Waste Container is of sound integrity. Attachment E lists each of the criteria from Appendix 2 and are checked off for each container.

NOTE 2 The integrity inspection of a waste container is to include the inspection of the bottom of the waste container.

NOTE 3 Any deterioration discovered during an inspection which may lead to an environmental or human health hazard shall be mitigated within 24 hours of discovery of the problem.

NOTE 4 Alert quality assurance specialist to properly document any nonconforming conditions associated with Waste containers.

§ [4] Conduct an integrity inspection of the waste container, checking (√) YES or NO for the inspection on Attachment E: (SR 4.4.1.3) (LCO 3.4.1.2)

[a] IF YES is checked for any integrity criteria designated with a \$ mark,
THEN perform the following:

1. Pause work and discontinue receipt of shipment.
2. Notify the PIC, TWF Operations Center, and RCT there is a waste container of questionable integrity in the shipment.
3. Check UNSAT for the inspected waste container in question.
4. Go to Step 5.1[34].

5.2 Inspection of Waste Containers (continued)

- [5] IF NO is checked for all criteria designated with a \$ mark,
THEN check SAT for the inspected waste container.
- [6] Return to Steps 5.1[26] or 5.1[33], as applicable.

5.3 Transfer and Storage of Waste Containers

Waste Handler Operator

NOTE 1 Steps 5.3[1][a] through 5.3[1][p] may be performed simultaneously for multiple payloads.

NOTE 2 Any waste container known to contain free liquids is to be placed on a secondary containment pallet in the destination WSB. If a container is known to contain free liquids, it cannot remain for longer than 24 hours. (LANL Permit 3.14.1(1))

- &** [1] IF transfer(s) is/are to a WSB,
THEN perform the following:
- [a] Initiate WCATS Intra Facility Transfer to destination WSB.
  - [b] Scan/input the TRU Waste Container(s) ID.
  - [c] Sign off on Intrafacility Transfer, recording task date and time on Attachment H.
  - [d] Record INTRA FACILITY TRANSFER TASK ID on Attachment H.
  - [e] Record the payload #, destination WSB, Task ID(s), and waste container number(s) on an Attachment F, *MAR Limit for WSBs*.

NOTE Performing a Test Execute in WCATS will verify the MAR Surveillance Requirements.

- \$** [f] Verify MAR in the affected individual WSB is $\leq 2,720$ PE-Ci as waste (SR 4.2.1.1)
- [g] Circle SAT or UNSAT on Attachment F.
- [h] IF SAT is circled,
THEN perform the following:
- 1. Initial on Attachment F.
  - 2. Sign off on the COMPLETED BY section of Attachment F.
- [i] IF UNSAT is circled,
THEN perform the following:
- 1. Pause work.

5.3 Transfer and Storage of Waste Containers (continued)

2. Notify the PIC and TWF Operations Center.
3. Initial on Attachment F.
4. Document in COMMENTS sections of Attachment F.
5. Sign off on the COMPLETED BY section of Attachment F.
6. Wait for further instructions from the Operations Center.

[j] Verify with the RCT that all waste containers on this payload are cleared for transfer.

NOTE 1 When performing stacking operations, securing a payload is required, and payloads in that stack must be banded.

\$ NOTE 2 In accordance with SAC 5.9.1 - Except for POCs, a PAYLOAD SHALL be limited to one of the following configurations:

- A maximum of four (4) drums (TRU Waste Containers)
- Only one (1) SWB/SLB2 (either an OVERPACKED SWB or a direct-loaded SWB/SLB2) (**SAC 5.9.1**)

NOTE 3 In accordance with SAC 5.9.1 Basis - there are no restrictions associated with POCs in a payload.

[k] **SECURE** a payload that meets the following restrictions.

\$ • A maximum of four (4) drums (TRU Waste Containers) on a single pallet (SAC 5.9.1)

\$ • Only one (1) SWB/SLB2 (either an OVERPACKED SWB or a direct-loaded SWB/SLB2) on a single pallet (**SAC 5.9.1**)

• A maximum of four (4) POCs on a single pallet

[l] IF any waste container(s) are scheduled to be placed on the third tier, THEN perform a High-Consequence Material Handling Activity in accordance with TWF-FO-DOP-2003.

[m] Contact the Operations Center and request verification that the Intra-Facility Transfer WCATS Task ID indicates the correct destination (WSB/CWSB) was selected using WCATS Desktop Application.

5.3 Transfer and Storage of Waste Containers (continued)

[n] Move waste container(s)/pallet(s) to the specific WSB location, ensuring all transferred waste container(s)/pallet(s) are within the Combustible Loading Boundary (CLB).

1. Unstrap payloads as necessary.

[o] IF additional banding is required after moving waste container(s)/pallet to the WSB,
THEN refer to TWF-WO-DOP-3007.

[p] IF additional waste containers are to be transferred to a WSB,
THEN return to Step 5.3[1][a] for each Task ID.

NOTE Steps 5.3[2][a] through 5.3[2][p] may be performed simultaneously for multiple payloads.

[2] IF transfer(s) is/are to the CWSB,
THEN perform the following:

[a] Initiate WCATS Intra Facility Transfer to CWSB.

[b] Scan/input the TRU Waste Container ID(s).

[c] Sign off on Intrafacility Transfer, recording task date and time on Attachment H.

[d] Record INTRA FACILITY TRANSFER TASK ID on Attachment H.

[e] Record the payload #, Task ID, and waste container number(s) on an Attachment G, *MAR Limit for the CWSB*.

NOTE Performing a Test Execute in WCATS will verify the MAR Surveillance Requirements.

§ [f] Verify MAR in the CWSB is $\leq 2,880$ PE-Ci as waste (SR 4.2.1.2).

[g] Circle SAT or UNSAT on Attachment G.

[h] IF SAT is circled,
THEN perform the following:

1. Initial on Attachment G.

2. Sign off on the COMPLETED BY section of Attachment G.

5.3 Transfer and Storage of Waste Containers (continued)

- [i] IF UNSAT is circled,
THEN perform the following:
1. Pause work.
  2. Notify the PIC and TWF Operations Center.
  3. Initial on Attachment G.
  4. Document in COMMENTS sections of Attachment G.
  5. Sign off on the COMPLETED BY section of Attachment G.
  6. Wait for further instructions from the Operations Center.

§ **NOTE 1** When performing stacking operations, securing a payload is required, and payloads in that stack must be banded.

NOTE 2 In accordance with SAC 5.9.1 - Except for POCs, a PAYLOAD SHALL be limited to one of the following configurations:

- A maximum of four (4) drums (TRU Waste Containers)
- Only one (1) SWB/SLB2 (either an OVERPACKED SWB or a direct-loaded SWB/SLB2) (**SAC 5.9.1**)

NOTE 3 In accordance with SAC 5.9.1 Basis - there are no restrictions associated with POCs in a payload.

[j] Verify with the RCT that all waste containers on this payload are cleared for transfer.

[k] Secure a payload that meets the following restrictions:

- §
- A maximum of four (4) drums (TRU Waste Containers) on a single pallet (**SAC 5.9.1**)
- §
- Only one (1) SWB/SLB2 (either an OVERPACKED SWB or a direct-loaded SWB/SLB2) on a single pallet (**SAC 5.9.1**)
  - A maximum of four (4) POCs on a single pallet

[l] IF any waste container(s) is/are scheduled to be placed on the third tier,
THEN perform a High-Consequence Material Handling Activity in accordance with TWF-FO-DOP-2003.

[m] Contact the Operations Center, and request verification that the Intra-Facility Transfer WCATS Task ID indicates the correct destination (WSB/CWSB) was selected using WCATS Desktop Application.

5.3 Transfer and Storage of Waste Containers (continued)

- & NOTE** Any waste container known to contain free liquids is to be placed on a secondary containment pallet in the CWSB for no longer than 24 hours (LANL Permit 3.14.1(1)).
- [n] Move waste container(s)/pallets(s) to the CWSB, unstrapping payloads as necessary.
  - [o] IF additional banding is required after moving waste container(s)/pallet to the CWSB,
THEN refer to TWF-WO-DOP-3007.
  - [p] IF additional waste containers are to be transferred to the CWSB,
THEN return to Step 5.3[2][a].
  - [3] IF no additional waste containers are to be transferred to a WSB/CWSB,
THEN sign off on the PERFORMED BY section of Attachment H.
  - [4] Perform an organize task on the waste containers in all destination WSBs/CWSB in accordance with WCATS.
  - [5] Notify RCTs that all transfers are complete.
  - [6] Ensure all rollup doors are closed in WSBs / CWSB.
  - &** [7] WHEN all transfers are complete,
THEN notify the Operations Center that a RCRA inspection is to be performed on the applicable WSB/CWSB.
  - [8] Notify Packaging and Transportation (P&T) to remove the transport vehicle(s) from the TWF Site.
  - [9] Ensure all Attachments are signed, complete, and turned in to the Operations Center.

Operations Center

- [10] Verify all Attachments are complete.
- [11] Document acceptance on Attachments A through G with printed name, signature, Z#, and date.
- [12] WHEN completing Attachment B and Attachment E,
THEN perform the following:
  - [a] Notify the Cognizant System Engineer (CSE) to review results.
  - [b] Document name of the CSE notified and date on the applicable attachment(s).

5.3 Transfer and Storage of Waste Containers (continued)

- [c] Provide the completed results to the CSE for review.

CSE

- [13] WHEN reviewing Attachment B and Attachment E,
THEN perform the following:
  - [a] IF applicable,
THEN disposition any deficiencies and document disposition on the applicable attachment(s).
  - [b] Sign and add Z#, date, and time to the applicable attachment(s).
  - [c] Return the applicable attachment(s) to the Operations Center.

SOS

- [14] Review and accept Attachments A through I as complete.
- [15] Document on the applicable attachments with printed name, signature, Z#, date, and time.

SOM

- [16] WHEN reviewing Attachment B and Attachment E,
THEN perform an Operability Determination, as applicable.
  - [a] Record determination on Attachments B and E.
- [17] Review and accept Attachments A through I as complete.
- [18] Document on Attachments A through I with printed name, signature, Z#, date, and time.

5.4 Contingencies

5.4.1 Attachments B and E

Operations Center with Operations Manager/SOM and TWF CSE

- [1] Evaluate the deficiency as to its impact on the Authorization Basis (operability determination, Limiting Condition for Operation [LCO]).
- [2] Initiate appropriate action.

Operations Center

- [3] For all deficiencies found during the performance of Attachment B and E, perform the following:
  - [a] Ensure that a Non-Conformance Report (NCR) has been initiated.
  - [b] Track all deficiencies (with associated NCR numbers) on the equipment status board in the Operations Center.

5.4.2 Attachments A, C, D, F, and G

Operations Center with SOM and TWF Subject Matter Expert (SME)

- [1] Evaluate the deficiency as to its impact on the Authorization Basis (operability determination, LCO).
- [2] Initiate appropriate action.

Operations Center

- [3] For all deficiencies found during the performance of Attachments A, C, D, F and G, perform the following:
  - [a] Ensure that a NCR has been initiated.
  - [b] Track all deficiencies (with associated NCR numbers) on the equipment status board in the Operations Center.

6.0 POST-PERFORMANCE ACTIVITIES

6.1 Post Job Review

[1] Conduct a post job review in accordance with TWF-FO-AP-2002.

6.2 Restoration

Not Applicable

6.3 Results

Results are documented in the Waste Compliance and Tracking System.

6.4 Verification/Independent Verification

Not Applicable

7.0 DEFINITIONS AND ACRONYMS

7.1 Definitions

Term	Definition
\$	When located in far left hand margin identifies steps that implement Technical Safety Requirements.
&	Identifies LANL Hazardous Waste Facility Permit Requirements or other environmental regulatory requirements.
CS	Identifies the direct implementation of a criticality safety administrative requirement.
Contact-Handled Transuranic Waste	Transuranic waste with a surface dose rate not greater than 200 millirem per hour. (Public Law 102-570)
Ensure	To confirm, substantiate and assure that an activity or consideration has been implemented in conformance with the specified requirements.
Remote Handled Transuranic Waste	Transuranic waste with a surface dose rate of 200 millirem per hour or greater. (Public Law 102-570)
Shall	Denotes a requirement
Should	Denotes a recommendation
Verify	To confirm and substantiate that an activity or condition has been implemented in conformance with the specified requirements. Manipulation of equipment or instrumentation to conform to the specified requirement is not permitted. Methods other than direct observation may be used.

7.2 Acronyms

Term	Definition
AC	Administrative Control
ALARA	As Low as Reasonably Achievable
CSE	Cognizant System Engineer
CWSB	Characterization and Waste Storage Building
EPC-WMP	Environmental Protection and Compliance Division, Waste Management Programs Group
FGE	Fissile Gram Equivalent
FOD	Facilities Operations Director
LAMCAS	Los Alamos Materials Control and Accountability System
LANMAS	Local Area Nuclear Material Accountability Software
LCO	Limiting Condition for Operation
MAR	Material at Risk
NCR	Non-Conformance Report
NMCA	Nuclear Material Control and Accountability
OC	Operations Center (TWF)
P&T	Packaging and Transportation
PIC	Person in Charge
POC	Pipe Overpack Container
RCRA	Resource Conservation and Recovery Act
RCT	Radiological Control Technician
RLM	Responsible Line Manager
RWP	Radiological Work Posting
SAC	Specific Administrative Control
SAT	Satisfactory
SLB2	Standard Large Box 2
SOM	Shift Operations Manager
SOS	Shift Operations Supervisor
SR	Surveillance Requirements
SWB	Standard Waste Box
TRU	Transuranic
TSD	Transportation Safety Document
TSR	Technical Safety Requirements
TWF	Transuranic Waste Facility

7.2 Acronyms (continued)

Term	Definition
TWSR	Transuranic Waste Storage Record
UNSAT	Unsatisfactory
WCATS	Waste Compliance and Tracking System
WIPP	Waste Isolation Pilot Plant
WSB	Waste Storage Building

8.0 RESPONSIBILITIES

8.1 Operations Center Operator

- Responsible for the overall coordination and final acceptance of this procedure
- If deficiencies are reported, documents the deficiencies and makes appropriate notifications
- Retains and submits records in accordance with EP-AP-10003, *Records Management*

8.2 Shift Operations Manager

- Ensures work performed is within the scope of the TWF approved procedures
- Keeps the FOD informed of the operational status of the facility
- Reviews completed Attachments for accuracy and signs

8.3 Shift Operations Supervisor

- Provides direction and leadership to assigned personnel for facility operations

8.4 Waste Handler Operator

- Ensures they are working to the most current revision of this procedure
- Performs TWF operations in accordance with facility procedures and standards
- Notifies and interfaces with Operations Center and SOS for procedure performance

8.5 Cognizant System Engineer

- Performs evaluation of deficiencies, reviews the completed and accepted surveillance and ensures Non-Conformance Reports are initiated as needed

8.6 Person In Charge

- Performs the Pre-Job Brief and Post-Job Review in accordance with TWF-FO-AP-2002

9.0 REFERENCES

Document Number	Title
DOE memo June 29, 1998	<i>Defense Programs Policy Guidance on Waste Management</i> (stored in history file for TWF-WO-DOP-3000, R3)
DOE-STD-5506- 2007, Table 4.4.1-1	<i>Payload Container Integrity Checklist</i>
E-Mail 04/27/2017	<i>Criticality Safety Comment</i> (stored in history file for TWF-WO-DOP-3000, R3)
EP-PA-10003	<i>Records Management</i>
LA-UR-18-23024	<i>Oxidizer Test Results for Cheesecloth (Cellulose) Exposed to 12.0 M Nitric Acid</i>
NCS-CSED-16-014	<i>Criticality Safety Evaluation for the Transuranic Waste Facility at TA-63</i>
NCS-CSED-14-133	<i>Criticality Safety Evaluation for Onsite Transfers of Fissile Waste Material</i>
NM Memo	<i>NM Hazardous Waste Bureau Memo May 17, 2018</i>
NM0890010515	<i>LANL Hazardous Waste Facility Permit</i>
P101-4	<i>Forklifts and Powered Industrial Trucks</i>
P101-18	<i>Procedure for Pause/Stop Work</i>
P300	<i>Integrated Work Management</i>
PA-DOP-01939	<i>TWF Operations Round Sheet</i>
POC-SPC-0001	<i>Specification for Fabrication of the Pipe Overpack (Standard, S100, S200 and S300)</i>
Public Law 102-570	<i>The Waste Isolation Pilot Plant Land Withdrawal Act</i>
SER TA-63 TWF, R0	<i>Safety Evaluation Report for the TA-63 TWF DSA/TSR</i>
TA55-RD-585	<i>Nuclear Materials Control and Accountability Requirements</i>
TWF-CSP-1009	<i>TWF Waste Operations</i>
TWF-FO-AP-2002	<i>TWF Pre-Job Briefings</i>
TWF-FO-AP-2006	<i>TWF Nuclear Criticality Safety Administration</i>
TWF-FO-DOP-2003	<i>TWF/RANT Forklift Operations</i>
TWF-WO-DOP- 3007	<i>TWF Banding Activities</i>
WIPP-02-3122	<i>Transuranic Waste Acceptance Criteria for the Waste Isolation Pilot Plant</i>
WIPP-11-3384	<i>CBFO Approved Filter Vents</i>
40 CFR 260.10	<i>Hazardous Waste Management System: General: Definitions</i>
49 CFR 173.465	<i>Type A Packaging Tests for DOT Specification, Type A Packaging</i>

10.0 RECORDS

Records generated as a result of implementing this procedure are maintained in accordance with EP-AP-10003.

Record Identification	Record Type Determination	Temporary Storage Method and Location	Disposition
Attachment A, <i>TWF Waste Container MAR Verification</i>	QA Record	Records shall be maintained in a metal file cabinet in the TWF Operations Center when <u>not</u> in use.	Completed record provided to Operations Center and retained in accordance with the retention schedule.
Attachment B, <i>TWF TRU Waste Container Metal/Type A Inspection</i>			
Attachment C, <i>TWF Site and Shipping & Receiving Area MAR Verification</i>			
Attachment D, <i>TWF Fueled Vehicle Inspection</i>			
Attachment E, <i>TWF Waste Container Receipt Data Sheet</i>			
Attachment F, <i>MAR Limit for WSBs</i>			
Attachment G, <i>MAR Limit for the CWSB</i>			
Attachment H, <i>Task ID Recording</i>			
Attachment I, <i>Criticality Safety Verifications</i>			
Attachment J, <i>Pre-Shipment Verifications</i>			
WCATS Inventory Report	Non-quality Record	Records SHALL have a reasonable level of protection to prevent loss and degradation.	Discard when no longer needed.

11.0 APPENDICES AND ATTACHMENTS

Appendix	Title
1	<i>WIPP Approved Vent Filters</i>
2	<i>TRU Waste Metal Containers Integrity Checklist</i>

Attachment	Title
A	<i>TWF Waste Container MAR Verification</i>
B	<i>TWF TRU Waste Container Metal/Type A Inspection</i>
C	<i>TWF Site and Shipping & Receiving Area MAR Verification</i>
D	<i>TWF Fueled Vehicle Inspection</i>
E	<i>TWF Waste Container Receipt Data Sheet</i>
F	<i>MAR Limit for WSBs</i>
G	<i>MAR Limit for the CWSB</i>
H	<i>Task ID Recording</i>
I	<i>Criticality Safety Verifications</i>
J	<i>Pre-Shipment Verifications</i>

Appendix 1, WIPP Approved Vent Filters

(Page 1 of 1)

Approved vent filters are listed in DOE/WIPP-11-3384, *CBFO Approved Filter Vents*

EXAMPLES

Appendix 2, TRU Waste Metal Container Integrity Checklist

(Page 1 of 10)

NOTE This checklist is from DOE/WIPP-02-3122, *Transuranic Waste Acceptance Criteria for the Waste Isolation Pilot Plant*

TRU WASTE METAL CONTAINER Examination		Discussion of Criteria
1.	Is the payload container obviously degraded?	Obviously degraded means clearly visible and potentially significant defects in the payload container or payload container surface.
2.	Is there evidence that the payload container is, or has been, pressurized?	Pressurization can be indicated by a fairly uniform expansion of the sidewalls, bottom or top. Past pressurization can be indicated by a notable outward deflection of the bottom or top. Verify that the payload container is not warped.
3.	Is there any potentially significant rust or corrosion such that wall thinning, pinholes, or breaches are likely or the load bearing capacity is suspect?	Rust shall be assessed in terms of its type, extent, and location. Pitting, pocking, flaking, or dark coloration characterizes potentially significant rust or corrosion. This includes the extent of the payload container surface area covered, thickness, and if it occurs in large flakes or built-up (caked) areas. Rusted payload containers may not be accepted if: • Rust is present in caked layers or deposits • Rust is present in the form of deep metal flaking, or built-up areas of corrosion products In addition, the location of rust should be noted; for example, on a drum: top lid; filter region; locking chine; top one-third, above the second rolling hoop; middle one-third, between the first and second rolling hoops; bottom one-third, below the second rolling hoop; and on the bottom. Payload containers may still be considered acceptable if the signs of rust show up as: • Some discoloration on the payload container • If rubbed would produce fine grit or dust or minor flaking (such that wall thinning does not occur)
4.	Are any of the following apparent? • Wall thinning • Pin holes • breaches	Wall thinning, pin holes, and breaches can be a result of rust/corrosion (see discussion for #3).
5.	Are there any split seams, tears, obvious holes, punctures (of any size), creases, broken welds, or cracks?	Payload containers with obvious leaks, holes or openings, cracks, deep crevices, creases, tears, broken welds, sharp edges or pits, are either breached or on the verge of being breached. Verify that there is no warpage that could cause the container to be unstable or prevent it from fitting properly in the applicable package.

Appendix 2, TRU Waste Metal Container Integrity Checklist

(Page 2 of 10)

NOTE This checklist is from DOE-STD-5506-2007, Table 4.4.1-1, *Payload Container Integrity Checklist*

TRU WASTE METAL CONTAINER Examination		Discussion of Criteria
6.	Is the load-bearing capacity suspect?	The load-bearing capacity could be reduced for excessive rust (see discussion for #3), wall thinning (see discussion for #4), breaches, cracks, creases, broken welds, etc. (see discussion for #5).
7.	Is the payload container improperly closed?	Inspect the fastener and fastener ring (chine) if applicable for damage or excessive corrosion. Check the alignment of the fastener to ensure that it is in firm contact around the entire lid and the payload container will not open during transportation.
8.	Are there any dents, scrapes, or scratches that make the payload container's structural integrity questionable or prevent the top and bottom surfaces from being parallel?	Deep gouges, scratches, or abrasions over wide areas are not acceptable. If top and bottom surfaces are not parallel, this would indicate that the container is warped. Dents should be less than ¼ inch deep by 3 inches long and between ½ inch to 6 inches wide. All other dents must be examined to determine impact of structural integrity.
9.	Is there discoloration which would indicate leakage or other evidence of leakage of material from the payload container?	Examine the payload container regions near vents, top lid fittings, bottom fittings, welds, seams and intersections of one or more metal sheets or plates. Payload containers must be rejected if evidence of leakage is present.
10.	Is the payload container bulged?	For the purposes of this examination, bulging is indicated by: • A fairly uniform expansion of the sidewalls, bottom, or top (e.g., in the case of a drum, either the top or bottom surface protrudes beyond the planar surface of the top or bottom ring), • A protrusion of the side wall (e.g., in the case of a drum, beyond a line connecting the peaks of the surrounding rolling hoops or a line between a surrounding rolling hoop and the bottom or top ring), or • Expansion of the side wall (e.g., in the case of a drum, such that it deforms any portion of a rolling hoop).

Appendix 2, TRU Waste Metal Container Integrity Checklist

(Page 3 of 10)

Obviously
degraded
container lids

Obviously degraded means clearly visible and potentially significant defects in the payload container or payload container surface.

Appendix 2, TRU Waste Metal Container Integrity Checklist

(Page 4 of 10)

Top with a notable outward deflection indicating possible pressurization

Pressurization can be indicated by a fairly uniform expansion of the sidewalls, bottom or top. Past pressurization can be indicated by a notable outward deflection of the bottom or top. Verify that the drum is not warped.

Appendix 2, TRU Waste Metal Container Integrity Checklist

(Page 5 of 10)

Rust must be assessed in terms of its type, extent, and location. Pitting, pocking, flaking, or dark coloration characterizes potentially significant rust or corrosion. This includes the extent of the payload container surface area, covered, thickness, and, if it occurs in large flakes or built-up (caked) areas. Rusty payload containers may not be accepted if:

- Rust is present in caked layers or deposits
- Rust is present in the form of deep metal flaking, or built-up areas of corrosion products

Appendix 2, TRU Waste Metal Container Integrity Checklist

(Page 6 of 10)

**Hole/Breach
due to forklift**

Payload containers with obvious leaks, holes or openings, cracks, deep crevices, creases, tears, broken welds, sharp edges or pits, are either breached or on the verge of being breached

Appendix 2, TRU Waste Metal Container Integrity Checklist

(Page 7 of 10)

**Improperly closed
fastener**

Broken gasket seal

Inspect the fastener and fastener ring (chine), if applicable, for damage or excessive corrosion. Check the alignment of the fastener to ensure that it is in firm contact around the entire lid and the payload container will not open during transportation.

Appendix 2, TRU Waste Metal Container Integrity Checklist

(Page 8 of 10)

Deep gouges, scratches, or abrasions over wide areas are not acceptable. If top and bottom surfaces are not parallel, this would indicate that the container is warped. Dents should be less than ¼ inch deep by 3 inches long and between ½ inch to 6 inches wide. All other dents must be examined to determine impact of structural integrity.

Appendix 2, TRU Waste Metal Container Integrity Checklist

(Page 9 of 10)

This container shows signs of discoloration/rust on the lid that would indicate leakage that has subsequently dried-up/rusted.

Examine the container regions near vents, top lid fittings, bottom fittings, welds, seams and intersections of one or more metal sheets or plates. Payload containers must be rejected if evidence of leakage is present.

Appendix 2, TRU Waste Metal Container Integrity Checklist

(Page 10 of 10)

Uniform expansion of the top.
Top surface does not protrude beyond the
planer surface of the top ring.

For the purposes of this examination, bulging is indicated by:

- A fairly uniform expansion of the sidewalls, bottom, or top (e.g., in the case of a drum, either the top or bottom surface protrudes beyond the planar surface of the top or bottom ring,
- A protrusion of the side wall (e.g., in the case of a drum, beyond a line connecting the peaks of the surrounding rolling hoops or a line between a surrounding rolling hoop and the bottom or top ring), or
- Expansion of the side wall (e.g., in the case of a drum, such that it deforms any portion of a rolling hoop).

Attachment A, TWF Waste Container MAR Verification

(Page 1 of 9)

5.1[2][a] Pickup Report Number: _____

Sheet 1

[illegible]**Sheet 2**[illegible]

Attachment A, TWF Waste Container MAR Verification

(Page 2 of 9)

5.1[2][a] Pickup Report Number: _____

Sheet 3

[illegible]**Sheet 4**[illegible]

Attachment A, TWF Waste Container MAR Verification

(Page 3 of 9)

5.1[2][a] Pickup Report Number: _____

Sheet 5

[illegible]**Sheet 6**[illegible]

Attachment A, TWF Waste Container MAR Verification

(Page 4 of 9)

5.1[2][a] Pickup Report Number: _____

Sheet 7

[illegible]

Attachment A, TWF Waste Container MAR Verification

(Page 5 of 9)

5.1[2][a] Pickup Report Number: _____

NOTE: Verification of MAR limits in this Attachment can be verified using WCATS and/or shipping documentation.

[1] **VERIFY** the following LCO:

Each TRU WASTE CONTAINER SHALL meet the following MAR limits:

- $\text{DRUMS} \leq 80 \text{ PE-Ci}$

	Description	5.1[4] Results	5.1[4][a]1, 5.1[4][b]3 Initials:
\$	VERIFY the MAR in each drum is ≤ 80 PE-Ci (Prior to acceptance at the TWF SITE) (SR 4.2.2.1)	SAT	
		UNSAT	
		N/A	

[2] IF the LCO is not met,
THEN, **CONTACT** the Operations Center.

Comments:

Attachment A, TWF Waste Container MAR Verification

(Page 6 of 9)

5.1[2][a] Pickup Report Number: _____

[3] VERIFY the following LCO:

Each TRU WASTE CONTAINER SHALL meet the following MAR limits:

- Direct-Loaded SWB/SLB2 ≤ 300 PE-Ci.

§	Description	5.1[4] Results	5.1[4][a]1, 5.1[4][b]3 Initials:
	VERIFY the MAR in each direct-loaded SWB/SLB2 is ≤ 300 PE-Ci (Prior to acceptance at the TWF SITE) (SR 4.2.2.2)	SAT UNSAT N/A	

[4] IF the LCO is not met,
THEN, **CONTACT** the Operations Center.

Comments:

Attachment A, TWF Waste Container MAR Verification

(Page 7 of 9)

5.1[2][a] Pickup Report Number: _____

[5] VERIFY the following LCO:

Each TRU WASTE CONTAINER SHALL meet the following MAR limits:

- OVERPACKED SWB $\leq 1,000$ PE-Ci.

	Description	5.1[4] Results	5.1[4][a]1, 5.1[4][b]3 Initials:
§	VERIFY the MAR in each OVERPACKED SWB is ≤ 1,000 PE-Ci (Prior to acceptance at the TWF SITE) (SR 4.2.2.3)	SAT	
		UNSAT	
		N/A	

**[6] IF the LCO is not met,
THEN, CONTACT the Operations Center.**

Comments:

Attachment A, TWF Waste Container MAR Verification

(Page 8 of 9)

5.1[2][a] Pickup Report Number: _____

[7] VERIFY the following LCO:

Each TRU WASTE CONTAINER SHALL meet the following MAR limits:

- $\text{POC} \leq 1,800 \text{ PE-Ci.}$

§	Description	5.1[4] Results	5.1[4][a]1, 5.1[4][b]3 Initials:
	VERIFY the MAR in each POC is $\leq 1,800$ PE-Ci (Prior to acceptance at the TWF SITE) (SR 4.2.2.4)	SAT UNSAT N/A	

[8] IF the LCO is not met,
THEN, CONTACT the Operations Center.

Comments:

Attachment A, TWF Waste Container MAR Verification

(Page 9 of 9)

5.1[2][a] Pickup Report Number: _____

FACILITY OPERATOR				
5.1[4][a]2, 5.1[4][b]5 Completed By: Operator Name	Signature	Z#	Date	
OPERATIONS CENTER				
ACCEPT procedure as complete:				
5.3[11] Name	Signature	Z#	Date	
OPERATIONS CENTER REVIEW				
5.3[14] SOS Name	Signature	Z#	Date	Time
5.3[16][a] SOM Name	Signature	Z#	Date	Time

Attachment B, TWF TRU Waste Container Metal/Type A Inspection

(Page 1 of 2)

5.1[2][a] Pickup Report Number: _____

NOTE 1: This SR has a frequency designation of “*prior to accepting a non-POC TRU WASTE CONTAINER at the TWF SITE*”. This SR must be performed prior to the decoupling of the trailer from the truck, and while the waste shipment is still being managed by the requirements of the Transportation Safety Document.

NOTE 2: If there are no TRU Waste Containers within this shipment the following SR may be marked as N/A.

[1] **VERIFY** the following LCO:

TRU WASTE CONTAINERS, excluding POCs, SHALL be:

- Metal
- Of a design whose prototype met the test specified for DOT 7A/ Type A Packaging

	Description	5.1[6] Results	5.1[6][a]1, 5.1[6][b]3 Initials:
		SAT	
\$	VERIFY the TRU WASTE CONTAINER is metal and of a design whose prototype met the tests specified in 49 CFR 173.465, <i>Type A Packaging Tests</i> (Prior to accepting a non-POC TRU WASTE CONTAINER at the TWF SITE) (SR 4.4.1.1)	UNSAT	
		N/A	

[2] **IF** the LCO is not met,
THEN, **CONTACT** the Operations Center.

Comments:

Attachment B, TWF TRU Waste Container Metal/Type A Inspection

(Page 2 of 2)

5.1[2][a] Pickup Report Number: _____

FACILITY OPERATOR				
5.1[6][a]2, 5.1[6][b]5 Completed By: Operator Name	Signature	Z#	Date	
OPERATIONS CENTER				
ACCEPT procedure as complete:				
5.3[11] Name	Signature	Z#	Date	
5.3[12][b] CSE Notified to Review Results:	Name:		Date:	
CSE REVIEW				
Disposition of Deficiencies: List deficiencies and recommended actions below. Deficiencies can be grouped, but actions must address each deficiency. Enter "N/A" in the section below if no deficiencies were identified during the SR performance. Attach additional sheets as necessary. Attach a copy of an <i>Operability Determination Form</i> completed per AP-341-516, if performed.				
Deficiency Description	Disposition	Operable Y/N		
5.3[13][b] CSE Name	Signature	Z#	Date	Time
OPERATIONS CENTER REVIEW				
5.3[15] SOS Name	Signature	Z#	Date	Time
5.3[16] Immediate Operability Determination (circle one):		N/A	Operable	Inoperable
Attach a copy of an Operability Determination Form completed per AP-341-516, if performed.				
5.3[18] SOM Name	Signature	Z#	Date	Time

Attachment C, TWF Site and Shipping & Receiving Area MAR Verification

(Page 1 of 3)

5.1[2][a] Pickup Report Number: _____

NOTE Verification of MAR limits in this Attachment can be verified using WCATS and/or shipping documentation.

[1] VERIFY the following LCO:

MAR inventory SHALL meet the following limits:

- Total MAR in SHIPPING AND RECEIVING AREA: either
~~is~~ ≤ 1,240 PE-Ci as waste
OR
≤.42 PE-Ci as SEALED SOURCES

Description	5.1[7][h] Results	5.1[7][h]1.a, 5.1[7][h]2.c Initials:
VERIFY the MAR in the SHIPPING AND RECEIVING AREA is either ≤ 1,240 PE-Ci as waste <u>OR</u> ≤ 42 PE-Ci as SEALED SOURCES. (Prior to acceptance of MAR into the SHIPPING AND RECEIVING AREA) (SR 4.2.1.5)	SAT UNSAT	

[2] IF the LCO is not met,
THEN CONTACT the Operations Center.

Comments:

Attachment C, TWF Site and Shipping & Receiving Area MAR Verification

(Page 2 of 3)

5.1[2][a] Pickup Report Number: _____

[3] VERIFY the following LCO:

MAR inventory SHALL meet the following limits:

- Total TWF SITE MAR $\leq 19,180$ PE-Ci as waste **AND** ≤ 42 PE-Ci as SEALED SOURCES.

	Description	5.1[7][h] Results	5.1[5][h]1.a, 5.1[5][h]2.c Initials:
§	VERIFY the TWF SITE MAR is $\leq$ 19,180 PE-Ci as waste and $\leq$ 42 PE-Ci as SEALED SOURCES (Prior to acceptance of MAR into the TWF SITE) (SR 4.2.1.6)	SAT	
		UNSAT	

[4] IF the LCO is not met,
THEN CONTACT the Operations Center.

Comments:

Attachment C, TWF Site and Shipping & Receiving Area MAR Verification

(Page 3 of 3)

5.1[2][a] Pickup Report Number: _____

FACILITY OPERATOR				
5.1[7][h]1.b, 5.1[7][h]2.e Completed By: Operator Name	Signature	Z#	Date	
OPERATIONS CENTER				
ACCEPT procedure as complete:				
5.3[11] Name	Signature	Z#	Date	
OPERATIONS CENTER REVIEW				
5.3[15] SOS Name	Signature	Z#	Date	Time
5.3[18] SOM Name	Signature	Z#	Date	Time

Attachment D, TWF Fueled Vehicle Inspection

(Page 1 of 2)

5.1[2][a] Pickup Report Number: _____

[1] VERIFY the following LCO:

The following vehicles SHALL be prohibited in the TWF SITE with the exception of
1) emergency vehicles during a drill/exercise or actual emergency; 2) snow removal equipment;
and 3) transportation vehicles within the scope of the transportation safety document:

- a. fossil-fueled vehicles
  - b. bio-fueled vehicles
  - c. vehicles capable of speeds >10 mph
  - d. fossil/bio-fueled transportation vehicles capable of speeds > 10 mph during MAR
- HANDLING OPERATIONS **

	Description	5.1[12] Results	5.1[12][a]1, 5.1[12][b]3 Initials:
\$	VERIFY the LCO is met. (Prior to performing MAR HANDLING OPERATIONS) (SR 4.3.4.1)	SAT / UNSAT	

- [2] IF** the LCO is not met,
THEN CONTACT the Operations Center.

Comments:

** A reasonable time frame (order of minutes) is allowed to remove a transportation vehicle from the SHIPPING AND RECEIVING AREA after decoupling from a shipping trailer and to allow an incoming transportation vehicle to enter the SHIPPING AND RECEIVING AREA and couple to a shipping trailer.

Attachment D, TWF Fueled Vehicle Inspection

(Page 2 of 2)

5.1[2][a] Pickup Report Number: _____

FACILITY OPERATOR				
5.1[12][a]2, 5.1[12][b]5 Completed By: Operator Name	Signature	Z#	Date	
OPERATIONS CENTER				
ACCEPT procedure as complete:				
5.3[11] Name	Signature	Z#	Date	
OPERATIONS CENTER REVIEW				
5.3[15] SOS Name	Signature	Z#	Date	Time
5.3[18] SOM Name	Signature	Z#	Date	Time

Attachment E, TWF Waste Container Receipt Data Sheet

(Page 1 of 4)

NOTE 1 This page may be duplicated as necessary.**NOTE 2** If YES is checked for any integrity criteria designated with a \$ mark, the container is unsatisfactory (UNSAT). Any waste container of questionable integrity shall be reported to the PIC and RANT Operations Center.**NOTE 3** If NO or N/A is checked for all integrity criteria designated with a \$ mark, the container is satisfactory (SAT).**5.1[2][a]** Pickup Report Number: _____

Page _____ of _____

5.1[2][b] Waste Container ID#					
5.1[2][b] Waste Container Configuration	☐ 55 gal. drum ☐ 85 gal. drum ☐ Direct loaded SWB / SLB2 ☐ Over packed SWB ☐ POC	☐ 55 gal. drum ☐ 85 gal. drum ☐ Direct loaded SWB / SLB2 ☐ Over packed SWB ☐ POC	☐ 55 gal. drum ☐ 85 gal. drum ☐ Direct loaded SWB / SLB2 ☐ Over packed SWB ☐ POC	☐ 55 gal. drum ☐ 85 gal. drum ☐ Direct loaded SWB / SLB2 ☐ Over packed SWB ☐ POC	☐ 55 gal. drum ☐ 85 gal. drum ☐ Direct loaded SWB / SLB2 ☐ Over packed SWB ☐ POC
(\$) 5.1[24] Is the waste container all in one label marked to indicate it contains D001, D002, D003 waste or is a PCB label attached? (SR 4.2.3.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO
N/A if TRU Waste Containers(s) are not within this shipment. (\$) 5.2[2] Excluding POCs, does the installed, WIPP-approved, vent filter show any evidence of being clogged? (SR 4.4.1.3)	☐ YES ☐ NO ☐ N/A	☐ YES ☐ NO ☐ N/A	☐ YES ☐ NO ☐ N/A	☐ YES ☐ NO ☐ N/A	☐ YES ☐ NO ☐ N/A
N/A if POC(s) are not within this shipment. (\$) 5.2[3] If a POC, does the installed, WIPP-approved UltraTech 9424S filter on the outer container show any evidence of being clogged. (LCO 3.4.1.2)	☐ YES ☐ NO ☐ N/A	☐ YES ☐ NO ☐ N/A	☐ YES ☐ NO ☐ N/A	☐ YES ☐ NO ☐ N/A	☐ YES ☐ NO ☐ N/A
(\$) 5.2[4] Is the payload container obviously degraded? (SR 4.4.1.3) (LCO 3.4.1.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO
(\$) 5.2[4] Is there evidence that the payload container is, or has been, pressurized? (SR 4.4.1.3) (LCO 3.4.1.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO
(\$) 5.2[4] Is there any potentially significant rust or corrosion such that wall thinning, pinholes, or breaches are likely or the load bearing capacity is suspect? (SR 4.4.1.3) (LCO 3.4.1.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO

Attachment E, TWF Waste Container Receipt Data Sheet

(Page 2 of 4)

NOTE This page may be duplicated as necessary.**5.1[2][a]** Pickup Report Number: _____

Page _____ of _____

5.1[2][b] Waste Container ID#					
(S) 5.2[4] Are there any split seams, tears, obvious holes, punctures (of any size), creases, broken welds, or cracks? (SR 4.4.1.3) (LCO 3.4.1.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO
(S) 5.2[4] Is the payload container improperly closed? (SR 4.4.1.3) (LCO 3.4.1.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO
(S) 5.2[4] Are there any dents, scrapes, or scratches that make the container's structural integrity questionable or prevent the top and bottom surfaces from being parallel? (SR 4.4.1.3) (LCO 3.4.1.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO
(S) 5.2[4] Is there discoloration which would indicate leakage or other evidence of leakage of material from the payload container? (SR 4.4.1.3) (LCO 3.4.1.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO
(S) 5.2[4] Are any of the following apparent? • Wall thinning • Pin holes • Breaches (SR 4.4.1.3) (LCO 3.4.1.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO
(S) 5.2[4] Is the load-bearing capacity suspect? (SR 4.4.1.3) (LCO 3.4.1.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO
(S) 5.2[4] Is the payload container bulged? (SR 4.4.1.3) (LCO 3.4.1.2)	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO	☐ YES ☐ NO
N/A if TRU Waste Containers(s) are not within this shipment. (S) 5.2[2][a]3, 5.2[4][a]3, 5.2[5] The outer TRU WASTE CONTAINER is of sound integrity and a vent filter is installed on the outer container with no evidence of clogging (SR 4.4.1.3)	☐ SAT ☐ UNSAT ☐ N/A	☐ SAT ☐ UNSAT ☐ N/A	☐ SAT ☐ UNSAT ☐ N/A	☐ SAT ☐ UNSAT ☐ N/A	☐ SAT ☐ UNSAT ☐ N/A
N/A if POC(s) are not within this shipment. (S) 5.2[3][a]3, 5.2[4][a]3, 5.2[5] The POC is of sound integrity with an UltraTech 9424S filter installed on the outer container that shows no indication of clogging. [LCO 3.4.1.2]	☐ SAT ☐ UNSAT ☐ N/A	☐ SAT ☐ UNSAT ☐ N/A	☐ SAT ☐ UNSAT ☐ N/A	☐ SAT ☐ UNSAT ☐ N/A	☐ SAT ☐ UNSAT ☐ N/A

Attachment E, TWF Waste Container Receipt Data Sheet

(Page 3 of 4)

5.1[2][a] Pickup Report Number: _____

[1] **VERIFY** the following LCO:

TRU WASTE CONTAINERS, excluding POCs, SHALL be:

- Of sound integrity
- Vented

POCs SHALL be:

- Vented on the outer container with an UltraTech 9424S filter with no evidence of clogging
- Of sound integrity

§

Description	5.1[33][a], 5.1[34][a] Results	5.1[33][b], 5.1[34][b] Initials:
NOTE If there are no TRU Waste containers within this shipment the following SR may be marked as N/A.		
VISUALLY inspect the outer TRU WASTE CONTAINER to be of sound integrity and VERIFY that a vent is installed on the outer container with no evidence of clogging (Prior to TRANSFER of a TRU WASTE CONTAINER to the WASTE STORAGE AREA) (SR 4.4.1.3)	SAT UNSAT N/A	

[2] IF the LCO is not met,
THEN contact the Operations Center.**Comments:**

Attachment E, TWF Waste Container Receipt Data Sheet

(Page 4 of 4)

5.1[2][a] Pickup Report Number: _____

FACILITY OPERATOR				
5.1[33][d], 5.1[34][d] Completed By: Operator Name	Signature	Z#	Date	
Operator Name (N/A if not needed)	Signature	Z#	Date	
OPERATIONS CENTER				
ACCEPT procedure as complete:				
5.3[11] Name	Signature	Z#	Date	
5.3[12][b] CSE Notified to Review Results:	Name:		Date:	
CSE REVIEW				
Disposition of Deficiencies: List deficiencies and recommended actions below. Deficiencies can be grouped, but actions must address each deficiency. Enter "N/A" in the section below if no deficiencies were identified during the SR performance. Attach additional sheets as necessary. Attach a copy of an <i>Operability Determination Form</i> completed per AP-341-516, if performed.				
Deficiency Description	Disposition	Operable Y/N		
5.3[13][b] CSE Name	Signature	Z#	Date	Time
OPERATIONS CENTER REVIEW				
5.3[15] SOS Name	Signature	Z#	Date	Time
5.3[16][a] Immediate Operability Determination (circle one):		N/A	Operable	Inoperable
Attach a copy of an Operability Determination Form completed per AP-341-516, if performed.				
5.3[18] SOM Name	Signature	Z#	Date	Time

Attachment F, MAR Limit for WSBs

(Page 1 of 2)

5.1[2][a] Pickup Report Number: _____**NOTE 1** A group of palletized waste containers can have the MAR verified as a group before transferring to a WSB.**NOTE 2** This attachment must be used, and may duplicated, as necessary.**5.3[1][e]**

Payload #		WSB #	63 -	Task ID	
Waste Container #					
Waste Container #					
Waste Container #					
Waste Container #					
Payload #		WSB #	63 -	Task ID	
Waste Container #					
Waste Container #					
Waste Container #					
Waste Container #					
Payload #		WSB #	63 -	Task ID	
Waste Container #					
Waste Container #					
Waste Container #					
Waste Container #					

[1] **VERIFY** the following LCO:

MAR inventory SHALL meet the following limits:

- Total MAR in each WSB $\leq$ 2,720 PE-Ci as waste

	Description	5.3[1][g] Results	5.3[1][h]1, 5.3[1][i]3 Initials:
\$	VERIFY the MAR in the affected individual WSB is $\leq$ 2,720 PE-Ci as waste (prior to introduction of MAR into the affected WSB) (SR 4.2.1.1)	SAT	
		UNSAT	

[2] **IF** the LCO is not met,
THEN **CONTACT** the Operations Center.**Comments:**

Attachment F, MAR Limit for WSBs

(Page 2 of 2)

5.1[2][a] Pickup Report Number: _____

FACILITY OPERATOR				
5.3[1][h]2, 5.3[1][i]5 Completed By: Operator Name	Signature	Z#	Date	
OPERATIONS CENTER				
ACCEPT procedure as complete:				
5.3[11] Name	Signature	Z#	Date	
OPERATIONS CENTER REVIEW				
5.3[15] SOS Name	Signature	Z#	Date	Time
5.3[18] SOM Name	Signature	Z#	Date	Time

Attachment G, MAR Limit for the CWSB

(Page 1 of 2)

5.1[2][a] Pickup Report Number: _____**NOTE 1** A group of palletized waste containers can have the MAR verified as a group before transferring to the CWSB.**NOTE 2** This attachment must be used, and may duplicated, as necessary.**5.3[2][e]**

Payload #		Task ID	
Waste Container #			
Waste Container #			
Waste Container #			
Waste Container #			
Payload #		Task ID	
Waste Container #			
Waste Container #			
Waste Container #			
Waste Container #			
Payload #		Task ID	
Waste Container #			
Waste Container #			
Waste Container #			
Waste Container #			

[1] **VERIFY** the following LCO:

MAR inventory SHALL meet the following limits:

- Total MAR in the CWSB $\leq$ 2,880 PE-Ci as waste

\$	Description	5.3[2][g] Results	5.3[2][h]1, 5.3[2][i]3 Initials:
	VERIFY the MAR in the CWSB is $\leq$ 2,880 PE-Ci as waste (prior to introduction of MAR into the CWSB) (SR 4.2.1.2)	SAT UNSAT	

[2] **IF** the LCO is not met,
THEN **CONTACT** the Operations Center.**Comments:**

Attachment G, MAR Limit for the CWSB

(Page 2 of 2)

5.1[2][a] Pickup Report Number: _____

FACILITY OPERATOR				
5.3[2][h]2, 5.3[2][i]5 Completed By: Operator Name	Signature	Z#	Date	
OPERATIONS CENTER				
ACCEPT procedure as complete:				
5.3[11] Name	Signature	Z#	Date	
OPERATIONS CENTER REVIEW				
5.3[15] SOS Name	Signature	Z#	Date	Time
5.3[18] SOM Name	Signature	Z#	Date	Time

Attachment H, Task ID Recording

(Page 1 of 2)

5.1[2][a] Pickup Report Number: _____**NOTE** This attachment must be used, and may be duplicated as necessary.**Receipt at TWF****5.1[7][d]** Receipt Date and Time
_____/_____
Date Time**5.1[7][e]** WCATS Task ID No.:
_____
Task ID No.**Shipping and Receiving Area Receipt****5.1[36]** Receipt complete Date and Time:
_____/_____
Date Time**5.1[37]** WCATS Task ID No.:
_____
Task ID No.**NOTE 1** Each waste container transfer to a WSB generates an additional task ID in WCATS.**NOTE 2** Any unused spaces (Task ID No., Bldg. No., Time, Date) are to be N/A'd once all transfers are complete.**Transfer to WSBs Waste Staging Area****5.3[1][c]** Task Date and Time:
_____/_____
Date Time**5.3[1][d]** WCATS Task ID #:
_____
Task ID No. Bldg. No.**5.3[1][c]** Task Date and Time:
_____/_____
Date Time**5.3[1][d]** WCATS Task ID #:
_____
Task ID No. Bldg. No.**5.3[1][c]** Task Date and Time:
_____/_____
Date Time**5.3[1][d]** WCATS Task ID #:
_____
Task ID No. Bldg. No.**5.3[1][c]** Task Date and Time:
_____/_____
Date Time**5.3[1][d]** WCATS Task ID #:
_____
Task ID No. Bldg. No.**5.3[1][c]** Task Date and Time:
_____/_____
Date Time**5.3[1][d]** WCATS Task ID #:
_____
Task ID No. Bldg. No.

Attachment H, Task ID Recording

(Page 2 of 2)

5.1[2][a] Pickup Report Number: _____

NOTE 1 Each waste container transfer to a CWSB generates an additional task ID in WCATS.**NOTE 2** Any unused spaces (Task ID No., Time, Date) are to be N/A'd once all transfers are complete.**Transfer to CWSB Waste Staging Area**5.3[2][c] Task Date and Time: _____ / _____
Date Time5.3[2][d] WCATS Task ID #: _____
Task ID No.5.3[2][c] Task Date and Time: _____ / _____
Date Time5.3[2][d] WCATS Task ID #: _____
Task ID No.5.3[2][c] Task Date and Time: _____ / _____
Date Time5.3[2][d] WCATS Task ID #: _____
Task ID No.5.3[2][c] Task Date and Time: _____ / _____
Date Time5.3[2][d] WCATS Task ID #: _____
Task ID No.**Comments:**

5.3[3]Performed By: _____ / _____ / _____ / _____
Waste Handler Operator (print) Signature Z # Date Time**5.3[15]**Reviewed By: _____ / _____ / _____ / _____
Shift Operations Supervisor (print) Signature Z # Date Time**5.3[18]**Reviewed By: _____ / _____ / _____ / _____
Shift Operations Manager (print) Signature Z # Date Time

Attachment I, Criticality Safety Verifications

(Page 1 of 2)

5.1[2][a] Pickup Report Number: _____

- (CS) 3.1[2] bullet 2 There are ≤ 75 (waste) containers in the Shipping Trailer (transfer vehicle).
_____/_____
Initials Date
- (CS) 3.1[2] bullet 3 If > 75 containers are present (e.g., in another transfer vehicle or a storage array), each transfer vehicle is separated by > 10 feet from other arrays of waste containers.
_____/_____
Initials Date
- (CS) 3.1[2] bullet 13 No High Fissile Gram Equivalent (FGE) ^{239}Pu (drums / pipe overpacks > 200 FGE and SWBs > 325 FGE) containers are within this shipment according to WCATS “Pu-239 FGE [2U]” (Ref. E-Mail 04/27/2017, *Criticality Safety Comment*).
_____/_____
Initials Date
- (CS) 5.1[5] All waste containers in the Shipping Trailer are Type A metal (steel).
_____/_____
Initials Date
- (CS) 5.1[18] bullet 1 There are no open waste containers within the Shipping Trailer (transfer vehicle).
_____/_____
Initials Date
- (CS) 5.1[18] bullet 2 Waste containers within the Shipping Trailer (transfer vehicle) are not stacked greater than 3 high.
_____/_____
Initials Date
- (CS) 5.1[30] During waste container unloading, no waste containers are stacked greater than 3 high.
_____/_____
Initials Date

Attachment I, Criticality Safety Verifications

(Page 2 of 2)

5.1[2][a] Pickup Report Number: _____

Comments:

5.3[9]

Performed By: _____ / _____ / _____ / _____
Waste Handler Operator (print) Signature Z # Date Time

5.3[18]

Performed By: _____ / _____ / _____ / _____
Shift Operations Supervisor (print) Signature Z # Date Time

5.3[15]

Reviewed By: _____ / _____ / _____ / _____
Shift Operations Manager (print) Signature Z # Date Time

Attachment J, Pre-Shipment Verifications

(Page 1 of 3)

5.1[2][a] Pickup Report Number: _____

SOM or Designee

3.1[2] bullet 1 The following transfer paperwork has been obtained and verified:

- Shipment or Transfer Pickup Report from WCATS.

_____/_____
Initials Date

- Transuranic Waste Storage Record

_____/_____
Initials Date

- Type 7A Container Documentation

_____/_____
Initials Date

§ 3.1[2] bullet 3 No TRU waste containers within this shipment are greater than 200 mr/hr on contact (neutron + beta/gamma).

_____/_____
Initials Date

& 3.1[2] bullet 4 No mixed waste generated prior to April 21, 2011 are within this shipment.

_____/_____
Initials Date

§ 3.1[2] bullet 5 Only newly generated waste (December 31, 1998 and later) and no legacy waste (before December 31, 1998) are within this shipment. **(AC 5.8.9) (SR 4.2.3.1) (Ref. DOE Memo June 29, 1998)**

_____/_____
Initials Date

§ 3.1[2] bullet 6 All POCs within this shipment:

- Meet the criteria specified in Specification for Fabrication of Pipe Overpack (Standard, S100, S200 and S300 per POC-SPC-0001)
- Have a UltraTech 9424S vent filter installed on the outer container. **(SR 4.4.1.2)**

_____/_____
Initials Date

Attachment J, Pre-Shipment Verifications

(Page 2 of 3)

5.1[2][a] Pickup Report Number: _____

SOM or Designee

\$ 3.1[2] bullet 7 Each waste container's Waste Stream Profile is active (current) (utilizing WCATS Desktop Application). (SR 4.2.3.3)

_____/_____
Initials Date

\$ 3.1[2] bullet 8 No D001, D002, D003 coded waste or PCBs are within this shipment. (SR 4.2.3.2)

_____/_____
Initials Date

3.1[2] bullet 9 Every container on the shipment contains $\leq 1.0\%$ Beryllium.

_____/_____
Initials Date

& 3.1[2] bullet 10 No waste containers with greater than 1% free liquid, as defined in 40 CFR 260.10, are within this shipment.

_____/_____
Initials Date

3.1[2] bullet 11 Every container on the shipment is TRU Waste (>100 nCi/g).

_____/_____
Initials Date

3.1[2] bullet 13 The Technical Supervisor (TS) review (TS-REV) is complete and approved for each container in the WCATS Desktop Application.

_____/_____
Initials Date

3.1[2] bullet 14 The TRU Waste Facility Management Review (TWFWM-REV) is complete and approved for each container in the WCATS Desktop Application.

_____/_____
Initials Date

Comments:

3.1[3]

Performed By: _____/_____/_____/_____/_____
SOM or Designee (print) Signature Z # Date Time

Attachment J, Pre-Shipment Verifications

(Page 3 of 3)

5.1[2][a] Pickup Report Number: _____

Waste Handler Operator

5.1[7][a] The following electronic signatures are present on 63-TWF-RECV-TRU:

- Originating Facility Operator
- DOT Reviewer
- Onsite TSDF Transporter

Comments:

5.1[7][a]

Performed By: _____ / _____ / _____ / _____
Waste Handler Operator (print) Signature Z # Date Time