

LA-UR-21-25805

Approved for public release; distribution is unlimited.

Title: Vessel Fabrication Overview

Author(s): Gibson, Joshem Coy
Bingham, Kelly L.
Smouse, Thomas Dustin
Lopez, Frank Edward

Intended for: Presentation for Vessel Fabrication

Issued: 2021-06-21


Disclaimer:

Los Alamos National Laboratory, an affirmative action/equal opportunity employer, is operated by Triad National Security, LLC for the National Nuclear Security Administration of U.S. Department of Energy under contract 89233218CNA000001. By approving this article, the publisher recognizes that the U.S. Government retains nonexclusive, royalty-free license to publish or reproduce the published form of this contribution, or to allow others to do so, for U.S. Government purposes. Los Alamos National Laboratory requests that the publisher identify this article as work performed under the auspices of the U.S. Department of Energy. Los Alamos National Laboratory strongly supports academic freedom and a researcher's right to publish; as an institution, however, the Laboratory does not endorse the viewpoint of a publication or guarantee its technical correctness.

Vessel Fabrication Overview

Joshem Gibson, Kelly Bingham, Tom Smouse, Frank Lopez

June 2021




Mission Need

- LANL utilizes spherical vessels for numerous basic science, materials, and system performance experiments
- These pressure vessels are designed and fabricated to meet the *intent* of ASME B&PV Section VIII, Division 3 and Code Case 2564
 - LANL has successfully contracted vessel construction in the past, utilizing HSLA-100 steel
- As current vessel inventories approach design life, we are once again embarking upon a series of fabrication contracts to produce replacement components and vessel assemblies to support continued experiment cadence at LANL
- LANL's intent is to ramp up a continuous vessel supply chain for the DOE Complex



LANL Vessels

Ø6' Spherical – 5 port




Ø3' Spherical – 5 port



LANL Current Vessel Designs


Ø6' 5-Port Vessel



Production: 2-1/2" Thick Wall, ≈14,000 lbs

First Article: 2" Thick Wall, ≈ 11,000 lbs

Ø3' 5-Port Vessel



Production: 1-1/8" Thick Wall, ≈ 1,800 lbs

First Article: 1" Thick Wall, ≈ 1,600 lbs



Vessel Components (GFE)

Material: HSLA-100

- High Strength
- High Low Temperature Toughness
- Repairable: No Post-Weld Heat Treatment



Hemispherical Heads
(6' and 3')



Nozzle Ring Forgings
(Four Sizes Utilized)



Cover Disk Forgings
(Two Sizes Utilized)

Additional Fabrication Materials

LANL (GFE)


- Plate Provided for Welding Procedure & Performance Qualification

Subcontractor

- Weld Filler Metal & Other Consumables
- Fixturing
- Machining Consumables
- NDE Consumables
- Nuts, Bolts, O-rings & Misc. Hardware



Sample Vessel Construction Drawing



6ft





Contract Overview and Structure

Construction Contracts for 3' and 6' Vessels

- First Article (Current)
 - 6' Vessel First Article
 - Successful completion and acceptance qualifies subcontractor for production
 - 3' Vessel First Article
 - Successful completion and acceptance qualifies subcontractor for production
- Production
 - 6' Vessels (initial qty up to 20)
 - 3' Vessels (initial qty up to 9)
 - Forecasting On-going 2-3 Vessels/Year Beyond Initial Vessel Needs

Note: Each subcontractor must successfully meet all First Article technical performance criteria to be eligible/qualified for production contract awards. Successful First Article does not guarantee award of production contract.



First Article Vessel Construction Contract


Purpose and Scope:

- Expedite the Production Process
- First Article Contracts
 - Provide the means for a subcontractor to develop processes & procedures necessary to construct spherical vessels conforming to the requirements of ENG-TS-J2-1460 and First Article Vessel Design Drawings
 - Allows Subcontractor to implement and exercise all prerequisite processes for vessel production
 - Welding, Machining, NDE, Quality Assurance, and Documentation
 - Allows LANL to validate the effectiveness and ability of a subcontractor to comply with LANL's requirements, including:
 - ENG-TS-J2-1460
 - First Article Drawings



Selection Criteria for Vessel Construction Contract

- First Article
 - Successful completion and acceptable contract performance
- Quality Program
 - Verified during First Article
 - Established/approved prior to Production Award
- Cost and Schedule
 - Preference will be given for Lower Cost and Shorter Construction Duration



Summary of Technical Requirements

Specified Characteristics	Requirements	Verified by
First Article	To establish means & methods to meet requirements for production	See items below as well as LANL Specification ENG-TS-J2-1460
Material Chemical Composition	Weld Metal & HAZ	Chemical Composition & Microstructure Analysis, CMTR's
Mechanical Properties	Weld Metal & HAZ Strength, Hardness, Ductility, Toughness	Tensile, Brinell Hardness, Charpy Impact, Charpy Transition Curves Dynamic Tear Test, & CMTR's
Soundness	Weld Metal & HAZ Lack of weld & process defects	Wet Magnetic Particle & Ultrasonic & Radiographic Testing
Geometry	Fit & form must meet LANL drawing requirements	Dimensional Inspection & Test Reports
Process Control	QA Program, Submittals, Travelers, Procedures, Instructions and Qualification/Certifications	Subcontractor QA Program Qualification, Surveillance, Inspection & Test Reports



Timeline

- Contract Introduction Meetings as Scheduled with Subcontractor
- RFQ issued Aug. 2021
- Intent to Award 4 weeks after Proposal Submittal
- Develop Submittal Approval Schedule by 2 Weeks after Award
- Deliver First Article Components to Subcontractor by mid. Sept.
- Develop Welding Procedure by End of Oct.
- Develop Traveler and Inspection & Test Plan by end of Oct.
- Start Machining Vessel parts by mid Oct.
- Expectation of First Article Vessel complete by Mar. 2022
- Follow First Article Plan to do new Critical Programmatic Vessels
- 1st New Programmatic Vessel done by Dec. 2022



Current Vessel & Component Needs

Current 6' Vessel Component Needs							
Vessels Needed			Total of	20	1st Vessel	By	Mar. - 22
Description	Qty/vessel	Part Size	lbs/ piece	lbs / vessel	Qty PO	Weight PO	Tons PO
HSLA-100 Hemi-Heads	2	2.625" x 72" id.	6,800	13,600	41	278,800	139.4
HSLA-100 Nozzle	5	37.7" od x 23.2" id x 6.9"	1,400	7,000	100	140,000	70
HSLA-100 Cover Disks	5	34.7" od x 6.5"	1,800	9,000	112	201,600	101
Weld Metal lbs	916	Double U Joint Weld Filler	916	916	10,997	10,997	5.5
Total weight/ Vessel				30,516	Weight/ PO	631,397	315.70
Current 3' Vessel & Component Needs							
Vessels Needed			Total of	9	1st Vessel	By	Dec. -22
Description	Qty/Vessel	Part Size	lbs/ piece	lbs / vessel	Qty PO	Weight PO	Tons PO
HSLA-100 Hemi-Heads	2	1.25" x 36" dia.	900	1,800	19	17,100	8.55
HSLA-100 Top Nozzle	1	25" od x 15.5" id x 6.4"	600	600	11	6,600	3.30
HSLA-100 Top Cover	1	22" od x 6"	540	540	11	5,940	2.97
HSLA-100 Enter Nozzle	2	17.1" od x 5.2" id x 3.8	300	600	18	5,400	2.70
HSLA-100 Exit Nozzle	2	16.5" od x 9.48" id x 3.30"	280	560	18	5,040	2.52
HSLA-100 Base Ring	1	11" od x 5.4" id x 4"	126	126	9	1,134	0.57
Weld Metal lbs	121	Double U Joint Weld Filler	121	121	1,089	1,089	0.54
Weight/Vessel				2,547	Weight/ PO	25,203	12.60



Questions and Contacts

- Contract Questions
 - Larisa Gillis
 - larisak@lanl.gov
 - 1-505-709-0870 Cell
 - 1-505-709-8070 Office
- Technical Questions
 - Joshem Gibson
 - gibson@lanl.gov
 - 1-505-500-7520 Cell
 - 1-505-667-9970 Office
- QA Questions
 - Kelly Bingham
 - kellyb@lanl.gov
 - 1-505-620-9628 Cell

